

KALYANI ISPAT LIMITED

Registered Office : House No.- 117, Building No – N-18, First Floor, Sector-2, Near SBI ATM, Avanti Vihar, Raipur, Chhattisgarh, India- 492001 Phone: (06582) 256661, Fax : 91-6582-256442,
Email : rproffice@kalyaniispat.com
CIN: U27100CT2021PLC012353

Ref : KIL/ CG/ MOEF/25-26/06

Dated 23.05.2025

To,
The Scientist 'C'
Ministry of Environment, Forests & Climate Change (WCZ),
Arnaya Bhawan. North Block, Sector-19,
Naya Raipur Atal Nagar – 492002, Chhattisgarh.

Subject: Submission of Compliance report of the conditions imposed in Environmental Clearance of M/s. Kalyani Ispat Ltd. located at Village-Kopideh, Tehsil & Dist.- Rajnandgaon, State Chhattisgarh.

Ref.: EC identification no EC23A1001CG5286032N dated 08.05.2024

Sir,

With regards to the subject mentioned, please find enclosed the six monthly Compliance Report to the conditions laid in the Environmental Clearance for the period October 2024 to March 2025 for your kind perusal.

Thanking you,

Yours Sincerely,

For Kalyani Ispat Limited


P.K. Deo
Director

Enclosed: as above

Project	M/s Kalyani Ispat Limited
EC Identification No. and Date	EC 23A1001CG5286032N dated 08/05/2024
Period of compliance	October 2024 to March 2025

Note: Construction work started.

A. Specific conditions		
S.L	Conditions	Compliance statement
i.	This Environmental clearance is granted subject to final outcome of Hon'ble Supreme Court of India, Hon'ble High Court, Hon'ble NGT and any other Court of Law, if any, as may be applicable to this project.	Agreed
ii.	The project proponent shall comply with all the environmental protection measures and safeguards proposed in the documents submitted to the Ministry. All the recommendations made in the EIA/EMP in respect of environmental management, and risk mitigation measures relating to the project shall be implemented.	Agreed
iii.	The project proponent shall utilize modern technologies for capturing of carbon emitted and shall also develop carbon sink/carbon sequestration resources capable of capturing more than emitted. The implementation report shall be submitted to the IRO, MoEF&CC in this regard.	The same has been noted and will be complied with.
iv.	PP shall complete the conversion of the total proposed land for industrial use prior to commencement of proposed project.	Land is diverted in industrial purpose. Copy enclosed as Annexure- 1
v.	Village Kopedih is at 1.2 km, Kopedih Tedesara Rajnandgaon - Hospital at 1.5 km and other sensitive areas are within the study area of the project site. Proponent shall take appropriate environmental safeguard measures to minimize the impact on the habitation of the locals. The project proponent needs to strengthen green belt all around the plant area to reduce the dust pollution. The PP shall also include some of these locations in its environmental monitoring programme.	The same has been noted and will be complied with.
vi.	As committed, PP shall construct the bridge above the branch canal passing through the project area based on the NOC from concerned authority and there shall be no disturbance to the canal.	NOC obtained vide letter no 7106/Tak/ abhimat/ 2024 dated 23.12.2024. Copy enclosed as Annexure-2
vii.	PP shall make efforts for the conservation of the seasonal drain passing through project area.	Shall be complied.
viii.	Khapri Nala is at a distance of 0.3 km in North direction, minor irrigation tank at 0.7 km in West along with several other water bodies within the study area of the project site. A robust and full proof Drainage Conservation scheme to protect the natural drainage and its flow parameters; along with Soil conservation scheme and multiple Erosion control measures shall be implemented.	Shall be complied

ix.	Total water requirement of 4400 m ³ /day which will be obtained from the Surface Water from Shivnath River (at village Anjora) through pipeline after obtaining necessary permission from the Competent Authority.	495 KLD Ground water permission obtained from CGWA vide letter no CGWA/NOC/IND/EXP/2025/156 dated 04.02.2025 15 MLD Surface water permission obtained from Chhattisgarh State industrial Development Corporation Limited vide letter no CSIDC/ S 4 / 2022-2023/4392 dated 10.08.2022. Copy enclosed as Annexure -3
x.	Three tier Green Belt shall be Developed in at least 33% of the project area as per the committed plan all along the project site of adequate width and tree density shall not be less than 2500 per ha. Survival rate of green belt developed shall be monitored on periodic basis to ensure that damaged plants are replaced with new plants in the subsequent years. PP shall also develop greenbelt in the form of shelter belt comprising of total of 6 rows of 2x2 m plantation with tall trees & broad leaves with thick canopy along with windshield inside the plant premises to act as green barrier for air pollution & noise levels towards sensitive areas nearby project site. The PP shall also adopt vertical garden type of plantation. Compliance status in this regard, shall be submitted to concerned Regional Office of the MoEF&CC.	The same has been noted and will be complied with.
xi.	All the commitments made towards socio-economic development of the nearby villages shall be satisfactorily implemented. The action plan based on the social impact assessment study of the project as per the EMP in accordance to the Ministry's OM dated 30.09.2020 amounting to Rs. 14.15 Crores shall be strictly implemented and progress shall be submitted to the Regional Office of MoEF&CC.	Commitments made towards socio-economic development of the nearby villages will be implemented
xii.	The project proponent shall undertake village adoption programme and prepare and implement the action plan to develop them into a model village.	village adoption programme and implementation action plan to develop them into a model village will be completed
B.	General Conditions	
I.	Statutory Compliances:	
i.	The Environment Clearance (EC) granted to the project/ activity is strictly under the provisions of the EIA notification 2006 and its amendments issued from time to time. It does not tantamount / construe to approvals/ consent/permission etc. required to be obtained or standards/ conditions to be followed under any other Act/Rules/Subordinate legislations, etc., as may be applicable to the project.	Noted
ii.	This Environmental clearance is granted subject to final outcome of Hon'ble Supreme Court of India,	Noted

	Hon'ble High Court, Hon'ble NGT and any other Court of Law, if any, as may be applicable to this project.	
II.	Air Quality monitoring and preservation	
i.	The project proponent shall install 24 X 7 continuous emission monitoring system at process stacks to monitor stack emission as well as 04 Nos. Continuous Ambient Air Quality Station (CAAQS) for monitoring AAQ parameters with respect to standards prescribed in Environment (Protection) rules 1986 as amended from time to time. The CEMS and CAAQMS shall be connected to SPCB and CPCB online servers and calibrate these systems from time to time according to equipment supplier specification through labs recognized under Environment (Protection) Act, 1986 or NABL accredited laboratories.	Plant is under construction. 24 X 7 continuous emission monitoring system at process stacks to monitor stack emission will be installed. 04 Nos. Continuous Ambient Air Quality Station (CAAQS) will be installed
ii.	The project proponent shall carryout Continuous Ambient Air Quality monitoring for common/criterion parameters relevant to the main pollutants released (e.g. PM10 and PM25 in reference to PM emission, and SO2, and NOx in reference to SO2, and NOx emissions) within and outside the plant area (at least at four locations one within and three outside the plant area at an angle of 120° each) covering upwind and downwind directions.	Presently Environmental monitoring is being carried out by MOEF&CC recognized lab and report is enclosed as Annexure- 4 . 04 Nos. Continuous Ambient Air Quality Station (CAAQS) will be installed
iii.	The project proponent shall monitor fugitive emission in the plant premises at least once in every quarter through laboratories recognized under Environment (Protection) Act, 1986 or NABL accredited laboratories.	Fugitive emission monitoring is being carried out by laboratories recognized under Environment (Protection) Act, 1986 and report is enclosed as Annexure -5
iv.	Sampling facility at process stacks and at quenching towers shall be provided as per CPCB guidelines for manual monitoring of emissions.	Sampling facility at process stacks will be provided as per CPCB guidelines for manual monitoring of emissions.
v.	Appropriate Air Pollution Control (APC) system shall be provided for all the dust generating points including fugitive dust from all vulnerable sources, so as to comply prescribed stack emission and fugitive emission standards.	ESP and bag filter will be installed
vi.	The project proponent shall provide leakage detection and mechanized bag cleaning facilities for better maintenance of bags.	Leakage detection and mechanized bag cleaning facilities for better maintenance of bags will be provided
vii.	Sufficient number of mobile or stationary vacuum cleaners shall be provided to clean plant roads, shop floors, and roofs regularly.	Sweep machine will be provided to clean road
viii.	Ensure covered transportation and conveying of raw material to prevent spillage and dust generation. The project proponent use leak proof trucks/dumpers carrying coal and other raw materials and cover them with tarpaulin.	shall be complied
ix.	Recycle and reuse iron ore fines, coal and coke fines,	shall be complied

	lime fines and such other fines collected in the pollution control devices and vacuum cleaning devices in the process after briquetting /agglomeration	
x.	The project proponent shall provide primary and secondary fume extraction system at all heat treatment furnaces.	Fume extraction will be provided in SMS
xi.	Wind shelter fence and chemical spraying shall be provided on the raw material stock piles.	Wind shelter fence and chemical spraying will be provided on the raw material stock piles.
xii.	Design the ventilation system for adequate air changes as per prevailing norms for all tunnels, motor houses, Oil Cellars.	ventilation will be provided in Rolling mill
xiii.	Pollution control system in the plant shall be provided as per the CREP Guidelines of CPCB.	CREP Guidelines will be implemented
xiv	The project proponent shall adopt the Clean Air practices like mechanical collectors, wet scrubbers, fabric filters (bag houses), electrostatic precipitators, combustion systems (thermal oxidizers), condensers, absorbers, absorbers, and biological degradation. Controlling emissions related to transportation shall include emission controls on vehicles as well as use of cleaner fuels Sufficient numbers of additional truck mounted Fog/Mist water cannons shall be procured and operated regularly inside the project premises and also in the surrounding villages to arrest suspended dust in the atmosphere.	1. Company will adopt the Clean Air practices like mechanical collectors, wet scrubbers, fabric filters. 2. Electrostatic precipitators, combustion systems condensers, absorbers. 3. Sufficient numbers of additional truck mounted Fog/Mist water cannons shall be procured and operated regularly inside the project premises and also in the surrounding villages to arrest suspended dust in the atmosphere..
xv.	Bag filters shall be cleaned regularly and efficiency of bag filter system shall be monitored at regular intervals.	The same has been noted and will be complied with.
xvi.	Water Sprinklers/Water mist system shall be installed near raw material yards, operational units and other strategic locations to control fugitive emissions from the plant.	Water Sprinklers system will be installed near raw material yards, operational units and other strategic locations to control fugitive emissions from the plant.
xvii.	The particulate matter emissions from the process stacks shall be less than 30 mg/Nm ³ and measures shall be undertaken as per the submitted action plan. Efficient Air monitoring equipment shall be installed.	The same has been noted and will be complied with.
xviii.	Following additional arrangements to control fugitive dust shall be provided: a. Fog/Mist Sprinklers at all on bulk raw material storage area (at the transfer points) like Iron Ore, Coal and for Fly Ash and similar solid waste storage areas b. Proper covered vehicle shall be used while transport of materials c. Wheel washing mechanism shall be provided in	1. Wheel washing mechanism shall be provided in entry and exit gates with complete recirculation system 2. Proper covered vehicle will be used while transport of materials 3. Fog Sprinklers at all on bulk raw material storage area, Coal and

	entry and exit gates with complete recirculation system	for Fly Ash and similar solid waste storage areas
xix.	Briquetting and Jigging plant shall be installed in Ferro Alloys Plant.	Briquetting and jigging plant yet to install.
xx.	The PP shall minimize the evaporation losses in jigging operation to less than 10% using suitable advanced process.	Jigging plant yet to install.
xxi.	The 4th hole extraction system shall be provided in the Sub Merged Arc Furnaces and EAF.	The same has been noted and will be complied with.
xxii.	Industry is going to use silica quartz in large quantities and going to produce Silico Manganese and Ferro Silicon alloy steel. Therefore, it is necessary to control silica/quartz exposures at production Departments, not only emission norms as per Indian Factories Act. The permissible limit for silica/quartz should be within 10 mg/m ³ for total dust as per Indian Factories Act. Therefore, it is recommended to monitor personal and area exposures for silica quartz dust in the process plants.	Noted
xxiii.	No Ferro-chrome production shall be carried out without prior Environmental clearance from MoEF&CC.	Agreed
xxiv.	During operational phase at Captive Power Plant, Action Plan to monitor coke/coal dust exposures in different process plants using personal and area air samplers and to compare with permissible limits as per Indian Factories Act, 1948 shall be implemented.	During operational phase, Action Plan will be prepared to monitor coke/coal dust exposures in different process plants
xxv.	The coal dust should be monitored at coal unloading, crushing, furnace areas and should be within 2 mg/m ³ , respirable dust fraction containing less than 5% quartz as per Indian Factories Act, 1948.	coal dust will be monitored at coal unloading, crushing, furnace areas
xxvi.	Online stack monitoring system for IF and RHF shall be installed and monitoring report shall be submitted to the concerned Regional Office of the MoEF&CC along with the six monthly compliance report.	IF and RHF plant yet to install.
xxvii.	Low NO _x Burners will be installed at Reheating Furnace for control of Gaseous emissions generated while using PNG.	RHF plant yet to install.
III.	Water quality monitoring and preservation	
i.	The project proponent shall install 24x7 continuous effluent monitoring system with respect to standards prescribed in Environment (Protection) Rules 1986 vide G.S.R 277 (E) dated 31 st March 2012 (Integrated iron & Steel); G.S.R 414 (E) dated 30 th May 2008 (Sponge Iron) as amended from time to time; S.O. 3305 (E) dated 7 th December 2015 (Thermal Power Plants) as amended from time to time and connected to SPCB and CPCB online servers and calibrate these system from time to time according to equipment supplier specification through labs recognized	Effluent treatment plant yet to install.

	under Environment (Protection) Act, 1986 or NABL accredited laboratories.	
ii.	The project proponent shall monitor regularly ground water quality at least twice a year (pre and post monsoon) at sufficient numbers of piezometers/sampling wells in the plant and adjacent areas through labs recognized under Environment (Protection) Act, 1986 and NABL accredited laboratories	Ground water quality monitoring is being carried out by recognized under Environment (Protection) Act, 1986 and NABL accredited laboratories .
iii.	Garland drains and collection pits shall be provided for each stock pile to arrest the run-off in the event of heavy rains and to check the water pollution due to surface run off.	Garland drain is under construction
iv.	Water meters shall be provided at the inlet to all unit processes in the steel plants.	Water meters will be provided at the inlet to all unit processes in the steel plants.
v.	The project proponent shall make efforts to minimize water consumption in the plant complex by segregation of used water, practicing cascade use and by recycling treated water.	Agreed
vi.	The proposed project shall be designed as "Zero Liquid Discharge" Plant. ETP shall be installed and there shall be no discharge of effluent from the plant. Domestic effluent shall be treated in Sewage Treatment Plant. Suitable measures shall be adopted for sewage water handling to ensure no contamination of any kind of water body.	Agreed, Zero Liquid Discharge" Plant. ETP Will be installed no discharge of effluent from the plant.
vii.	All stockyards shall have impervious flooring and shall be equipped with water spray system for dust suppression. Stock yards shall also have garland drains and catch pits to trap the run off material and shall be implemented as per the action plan submitted in EIA/EMP report.	The same has been noted and will be complied with.
viii.	Rain water harvesting shall be implemented to recharge/harvest water as per the action plan submitted in the EIA/EMP report.	The same has been noted and will be complied with.
ix.	The project proponent shall provide the ETP for effluents of rolling mills to meet the standards prescribed in G.S.R 277(E) 31st March 2012 (applicable to IF/EAF) as amended from time to time.	Rolling Mill yet to be installed.
x.	Air Cooled condensers shall be used in the captive power plant.	Air Cooled condensers is being used in the captive power plant.
IV.	Noise monitoring and prevention	
i.	Noise pollution shall be monitored as per the prescribed Noise Pollution (Regulation and Control) Rules, 2000 and report in this regard shall be submitted to Regional Officer of the Ministry as a part of six-monthly compliance report.	Noise Monitoring is being carried out by MOEF&CC Recognized Lab. Report is enclosed as Annexure - 6
ii.	The ambient noise levels should conform to the standards prescribed under E(P)A Rules, 1986 viz. 75	Noise monitoring is well within limits

	dB(A) during day time and 70 dB(A) during night time	
iii.	PP shall identify extreme hot areas through heat stress survey as well as noise monitoring within process plants to ensure that workers not exposed above 90 dBA levels as per Factories Act, 1948.	Shall be complied
V.	Energy Conservation measures	
i.	Provide solar power generation on roof tops of buildings, for solar light system for all common areas, street lights, parking around project area and maintain the same regularly;	Shall be complied
ii.	Provide LED lights in their offices and residential areas.	Shall be complied
iii.	The project proponent shall provide waste heat recovery system (pre-heating of combustion air) at the flue gases of reheating furnaces.	WHRB based power Plant is under construction.
iv.	Practice hot charging of slabs and billets/blooms as far as possible.	Rolling mill and RHF yet to install.
v.	Ensure installation of regenerative/ recuperative type burners on all reheating furnaces.	Rolling mill and RHF yet to install.
VI.	Waste management	
i.	Oil Collection pits shall be provided in oil cellars to collect and reuse/recycle spilled oil. Oil collection trays shall be provided under coils on saddles in cold rolled coil storage area.	Oil Collection pits will be provided.
ii.	Kitchen waste shall be composted or converted to biogas for further use.	
iii.	100% utilization of fly ash shall be ensured. All the fly ash shall be provided to cement and brick manufacturers for further utilization and Memorandum of Understanding in this regard shall be submitted to the Ministry's Regional Office.	100% utilization of fly ash is ensured. All the fly ash will be used for cement and brick manufacturers
iv.	The Plastic Waste Management Rules 2016, inter-alia, mandated banning of identified Single Use Plastic (SUP) items with effect from 01/07/2022 In this regard, CPCB has issued a direction to all the State Pollution Control Boards (SPCBs)/Pollution Control Committees (PCCs) on 30/06/2022 to ensure the compliance of Notification published by Ministry on 12/08/2021 The technical guidelines issued by the CPCB in this regard is available at https://cpcb.nic.in/technical-guidelines-3/ All the project proponents are hereby requested to sensitize and create awareness among people working within the Project area as well as its surrounding area on the ban of SUP in order to ensure the compliance of Notification published by this Ministry on 12/08/2021. A report, along with photographs, on the measures taken shall also be included in the six monthly compliance reports being submitted by the project proponents.	Shall be complied
v.	A proper action plan must be implemented to dispose	Shall be complied

	of the electronic waste generated in the industry.	
vi.	Solid waste utilization a. PP shall install a slag crusher to convert steel slag into aggregate for use in construction industry, fine sand for use as flux in steel plant, sand in brick making and as lime in cement making. b. PP shall recycle/reuse solid waste generated in the plant as far as possible. c. Used refractories shall be recycled as far as possible.	Shall be complied
VII.	Green Belt	
i.	The project proponent shall prepare GHG emissions inventory for the plant and shall submit the programme for reduction of the same including carbon sequestration by trees.	The GHG emission inventory report will be prepared.
ii.	Project proponent shall submit a study report on Decarburization program, which would essentially consist of company's carbon emissions, carbon budgeting/ balancing, carbon sequestration activities and carbon capture, use and storage and offsetting strategies Further, the report shall also contain time bound action plan to reduce its carbon intensity of its operations and supply chains, energy transition pathway from fossil fuels to Renewable energy etc. All these activities/assessments should be measurable and monitor able with defined time frames.	A study report on decarburization program will be submitted.
iii.	Greening and Paving shall be implemented in the plant area to arrest soil erosion and dust pollution from exposed soil surface	Agreed.
VIII.	Public hearing and Human health issues	
i.	Emergency preparedness plan based on the Hazard identification and Risk Assessment (HIRA) and Disaster Management Plan shall be implemented.	Emergency preparedness plan based on the Hazard identification and Risk Assessment (HIRA) and Disaster Management Plan will be prepared
ii.	The project proponent shall carry out heat stress analysis for the workmen who work in high temperature work zone and provide Personal Protection Equipment (PPE) as per the norms.	stress analysis will be carried out for the workmen who will work in high temperature work zone and will be provided Personal Protection Equipment
iii.	Provision shall be made for the housing of construction labour within the site with all necessary infrastructure and facilities such as fuel for cooking, mobile toilets, mobile STP. Safe drinking water, medical health care, creche etc. The housing may be in the form of temporary structures to be removed after the completion of the project.	Provision is made for the housing of construction labour within the site with all necessary infrastructure and facilities such as fuel for cooking, mobile toilets, mobile. Safe drinking water, medical health care, provided. Temporary housing may be removed after the completion of the project
iv.	Occupational health surveillance of the workers shall be done on a regular basis and records maintained.	Occupational health surveillance of the workers will be done on a regular

		basis and records will be maintained.												
IX.	Environment Management													
i.	The project proponent shall comply with the provisions contained in this Ministry's OM vide F. No. 22-65/2017-IA.III dated 30/09/2020. As part of Corporate Environment Responsibility (CER) activity, company shall adopt nearby villages based on the socio-economic survey and undertake community developmental activities in consultation with the village Panchayat and the District Administration as committed.	Shall be complied												
ii.	The company shall have a well laid down environmental policy duly approve by the Board of Directors. The environmental policy should prescribe for standard operating procedures to have proper checks and balances and to bring into focus any infringements/deviation/violation of the environmental / forest / wildlife norms / conditions. The company shall have defined system of reporting infringements / deviation / violation of the environmental / forest / wildlife norms / conditions and / or shareholders / stake holders. The copy of the board resolution in this regard shall be submitted to the MoEF&CC as a part of six-monthly report.	Corporate Environmental Policy is prepared and enclosed as Annexure-7 . System for reporting of non-compliance of EC conditions to the Board of Directors. The non-compliances are being reported to Board of Directors and corrective as well as preventive actions are taken.												
iii.	A separate Environmental Cell both at the project and company head quarter level, with qualified personnel shall be set up under the control of senior Executive, who will directly to the head of the organization.	A separate Environment Management Cell has been established both at the project and company head quarter level, details of environmental cell at company head quarter level. <table border="1"> <thead> <tr> <th>S I</th><th>Name</th><th>Designation</th></tr> </thead> <tbody> <tr> <td>1</td><td>G.P. Sharma</td><td>Sr. GM (Env)</td></tr> <tr> <td>2</td><td>Dr Bal Bandhu</td><td>DGM (Geo)</td></tr> <tr> <td>3</td><td>Mr. Rajeev Kumar</td><td>Manager (Env)</td></tr> </tbody> </table>	S I	Name	Designation	1	G.P. Sharma	Sr. GM (Env)	2	Dr Bal Bandhu	DGM (Geo)	3	Mr. Rajeev Kumar	Manager (Env)
S I	Name	Designation												
1	G.P. Sharma	Sr. GM (Env)												
2	Dr Bal Bandhu	DGM (Geo)												
3	Mr. Rajeev Kumar	Manager (Env)												
iv.	Performance test shall be conducted on all pollution control system every year and report shall be submitted to integrated regional Office of the MoEF&CC.	Performance test will be conducted on all pollution control system every year and report will be submitted to Integrated Regional Office of the MoEF&CC Raipur .												
X.	Miscellaneous													

i.	The project proponent shall make public the environmental clearance granted for their project along with the environmental conditions and safeguards at their cost by prominently advertising it at least in two local newspapers of the District or State, of which one shall be in the vernacular language within seven days and in addition this shall also be displayed in the project proponent's website permanently.	The advertisement was published in English newspaper "Amrit Sandesh and Hindi newspaper "Tarun dated 10.05.2024. copy of advertisement is enclosed as Annexure- 8
ii.	The copies of the environmental clearance shall be submitted by the project proponents to the Heads of local bodies, Panchayats and Municipal Bodies in addition to the relevant offices of the Government who in turn has to display the same for 30 days from the date of receipt.	Copy of Environmental Clearance letter has been submitted to Collector Rajnandgaon vide letter no Kalyani Ispat/ EC/2024 dated 09.05.2024. Copy enclosed as Annexure -9
iii.	The project proponent shall upload the status of compliance of the stipulated environmental clearance conditions, including results of monitored data on their website and update to the same on half-yearly basis.	Six monthly compliance report is being uploaded in company's website www.kalyaniispat.com
iv.	The project proponent shall monitor the criteria pollutants level namely; PM10, SO2, NOx (ambient levels as well as stack emissions) or critical sectoral parameters, indicated for projects and display the same at a convenient location for disclosure to the public and put on the website of the company.	shall be complied
v.	Action plan for developing connecting and internal road in terms of MSA as per IRC guidelines shall be implemented.	shall be complied
vi.	The Project proponent shall submit six-monthly reports on the status of the compliance of the stipulated Environmental conditions on the website of the Ministry of Environment, Forest and Climate change at Environment clearances portal.	Six-monthly compliance report is being submitted to MOEF&CC Regional office, Raipur and being uploaded in Parivesh portal
vii.	The project proponent shall submit the environmental statement for each financial year in Form-V to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently and put on the website of the company.	Shall be submitted in due course of time
viii.	The project proponent shall inform the Regional Office as well as the Ministry, the date of financial closure and final approval of the project by the concerned authorities, commencing the land development work and start of production operation by the project.	It is submitted that this is a 100% self-financed project and therefore no loans have been taken from the banks. Thus, financial closure and final approval from any authority is not required.
ix.	The project proponent shall abide by all the commitments and recommendations made in the EIA/EMP report, commitment made during Public Hearing and also that during their presentation to the Expert Appraisal Committee.	Environmental protection measures and safeguards recommended in the EIA/EMP report are being implemented.

x.	The recommendations of the approved site-Specific wildlife management plan (in case of involvement of Schedule-I species) shall be implemented in consultation with the State Forest Department. The implementation report shall be furnished along with the six-monthly compliance report to the concerned Regional Office of the MoEF&CC.	Site specific wildlife is approved by PCCF Wild life vide letter no 153 dated 04.07.2025
xi.	The PP shall put all the environment related expenditure, expenditure related to Action Plan on the PH issues, and other commitments made in the EIA/EMP Report etc. in the company web site for the information to public/public domain. The PP shall also put the information on the left over funds allocated to EMP and PH as committed in the earlier ECs and shall be carried out and spent in next three years, in the company website for the information to public/public domain.	Agreed
xii.	No further expansion or modifications in the plant shall be carried out without prior approval of the Ministry of Environment, Forests and Climate Change (MoEF&CC).	Agreed
xiii.	The Regional office of this Ministry shall monitor compliance of the stipulated conditions. The project authorities should extend full cooperation to the officer(s) of the Regional Office by furnishing the requisite data/information/monitoring reports.	Agreed

अदालत श्री जितेन्द्र सिंह राजपूत विशेष कर्तव्यस्थ अधिकारी, परिवर्तित भूमि राजनांदगांव (छ.ग.)
(परिवर्तित भूमि पर पुर्ननिर्धारण, प्रब्याजी तथा जुर्माना का सुचनापत्र)

नोटिस प्रपत्र-बी

अनुविभागीय अधिकारी/रा.मा.क

बनाम

20230509070008/अ-2 2022-2023

श्री कल्याणी इत्याद लिमिटेड काय अधिस्त डिग्री कुमार यादव
ग्राम कोपेडीह प.ह.न. 62 रा.नि.म. रेसरा
तहसील राजनांदगांव जिला राजनांदगांव (छ.ग.)

(1) आपको सूचित किया जाता है कि निम्नांकित भूमि पर गैर- कास्तकारी उपयोग में लाये जाने के कारण राजस्व मामला क्रमांक 20230509070008/518/312 /अ-2 2022-2023 के अंतर्गत अनुविभागीय अधिकारी, राजनांदगांव के आदेश दिनांक 15/05/2023 के अनुसार निम्नलिखित पुर्ननिर्धारण (जमा) निर्धारण किया गया है:-

ग्राम का नाम मय बंदोबस्त नंबर/प. ह.न.	खसरा नंबर/सर्वे नंबर/प्लॉट नंबर	परिवर्तित भूमि का क्षेत्रफल	अंतिम रूप से निर्धारण किया गया संशोधित पुर्ननिर्धारण
ग्राम <u>कोपेडीह</u> प.ह.न. <u>62</u>	481/1, 481/3, 482, 483/1, 483/2, 483/3, 483/4, 483/5, 484, 485/3, 486/1, 486/2, 486/3, 487/1, 487/3, 491/2, 491/3, 492/1, 498, 499/1, 499/2, 499/3, 499/4, 499/5, 499/6, 499/7, 499/8, 499/9, 499/10, 502/2, 502/3, 503, 504/1, 504/2, 505/1, 505/2, 506/1, 506/2, 506/3, 506/4, 507/2, 509/1, 510/2, 510/4, 510/5, 511/2, 511/3, 559/1, 559/2, 560, 561, 562, 563, 564/1, 564/2, 564/3, 565, 567/1, 567/3, 567/4, 568/1, 568/2, 568/4, 570, 573/1, 573/2, 573/3, 574/1, 576, 583/1, 583/2, 583/4, 584/1, 585/1, 585/2, 585/4, 585/5, 586, 587, 588/3, 589, 590/1, 590/3, 590/4, 591, 594/1, 594/2, 594/3, 594/4, 595/1, 595/2, 595/3, 595/4, 595/5, 596/1, 596/2, 596/3, 597/1, 597/2, 598/1, 598/2, 598/3, 598/4, 600/2, 600/3, 861/3	0.4000, 0.2000, 0.0730, 1.2150, 1.7160, 0.8090, 0.1250, 1.0900, 0.2830, 0.2000, 0.3240, 0.1020, 0.2220, 0.1210, 0.1920, 0.2020, 0.2830, 0.5050, 0.5249, 0.0410, 0.2430, 0.0320, 0.1380, 0.0610, 0.6320, 0.0610, 0.0360, 0.0610, 0.0360, 0.0930, 0.930, 0.1900, 0.7130, 0.3930, 0.2020, 0.2190, 0.3329, 0.2020, 0.2570, 0.2020, 0.1210, 0.2320, 0.5340, 0.6870, 0.1130, 0.1130, 0.2100, 0.4210, 0.5990, 0.5980, 0.5100, 0.8900, 0.7930, 0.6220, 0.0280, 0.0240, 0.0280, 0.3850, 0.0610, 0.2020, 0.2020, 0.2760, 0.3240, 0.3240, 0.0890, 0.2020, 0.2790, 0.0810, 0.1420, 0.1980, 0.0970, 0.1050, 0.0970, 0.2540, 0.1050, 0.1580, 0.2100, 0.1050, 0.6800, 0.0730, 0.5990, 0.7090, 0.0610, 0.0450, 0.2630, 1.4410, 0.1980, 0.1980, 0.1980, 0.1130, 0.5060, 0.1780, 0.1140, 0.1780, 0.2350, 0.0600, 0.1940, 0.1940, 0.1940, 0.1130, 0.1130, 0.1210, 0.0900, 0.3400, 0.2340, 0.1700, 0.1700	औद्योगिक उपयोग हेतु पुर्न निर्धारण की वार्षिक राशि 2023-24 से प्रत्येक वर्ष 2022-23 से डेय होगा
	कुल 30.541 हेक्टेयर		

कुल खसरा नं. 861/2

चालान नंबर 181, 167, 168, 169, 165 दिनांक 23/05/2023 को परिवर्तित लगान 202670=00
रूपये प्रीमियम 1527050=00 अर्थदण्ड 2 रूपये पंचायत उपकर 101355=00 रूपये पर्यावरण
उपकर 22800=00 रूपये अधोसंरचना विकास उपकर 22800=00 रूपये खजाना 2022-23
तक दाखिल किया गया। उपरोक्तानुसार संबंधित हल्का पटवारी अभिलेख दुरुस्त करें।

टीप :- संक्षम प्राधिकारी द्वारा छ.ग. भू- राजस्व संहिता की धारा 59(2.5) के अंतर्गत निम्नलिखित शर्तों के
अध्याधीन भूमि 229 मी० प्रयोजन के लिए पुनःनिर्धारण किया गया।

- शर्त:- (1) नगर तथा ग्राम निवेश विभाग के निर्धारित अभिन्यास के अनुरूप और संबंधित विभागों से
अनापत्ति/अनुमति प्राप्त करना, भूमि पर विकास/भवन निर्माण स्वीकृत कराना तथा नगर
निवेश का पत्र क्रमांक 2 दिनांक 2 के प्रावधानों का
पालन करना होगा।
- (2) उक्त भूमि पर भवन निर्माण / विकास हेतु नगर पालिका / अन्य संबंधित
विभागों से स्वीकृति प्राप्त करना होगा।
- (3) उक्त खसरा नंबर का बिना अभिन्यास अनुमोदन के भूमि का उप विभाजन नहीं किया जाये।
- (4) प्रकरण में नक्शे में दर्शाये भूमि पर दी गई शर्तों के अधीन निर्माण करना होगा।
आवेदित स्थल पर ऐसा कोई कार्य नहीं करेगा, जिससे आसपास के निवासियों के लिए न्यूसेंस
अथवा प्रदूषण उत्पन्न करें।
शुद्धीय भूमि पर अतिक्रमण न किया जावे।
प्रत्येक वर्ष नियमित रूप से परिवर्तित लगान की राशि संबंधित तहसील कार्यालय में जमा किया
जाना आवश्यक होगा।



जारी दिनांक 25/05/2023


अधीक्षक
भू-अभिलेख (परि.भूमि)
राजनंदगांव (छ.ग.)

**कार्यालय अनुवि भागीय अधिकारी (राजस्व), राजनांदगांव,
जिला-राजनांदगांव, छत्तीसगढ़
// सूचना पत्र प्रारूप "ब" //**

राजस्व मा0 क्र0/202403090700053/363, वर्ष- 2023-24 आदेश दिनांक 22/07/2024

आवेदक कल्याणी इरपात लिमिटेड द्वारा अधिकृत दिनेश कुमार यादव पिता श्री कुलदीप सिंह यादव, निवासी एस0 एच0-11, गार्डन ग्रूव, लालपुर, देवोपुरी, रायपुर, तहसील व जिला रायपुर (छत्तीसगढ़) आपको सूचित किया जाता है कि राजनांदगांव विकास योजना पुनर्विलोकन 2031 अनुसार निवेश क्षेत्र से बाहर है। अतः निम्नलिखित भूमि अकृषि कार्य में परिवर्तन होने के कारण उस पर निम्न अनुसूचित के खण्ड-5 में दिए अनुसार संशोधित राजस्व निर्धारण हो चुका है। जिसकी यथा विधि पुष्टिकरण हो गई है।

ग्राम कोपेडीह, पटवारी हल्का नंबर 62, खसरा नंबर क्रमशः 491/6, 491/7, 511/1, 511/4, 568/3, 569, 574/2, 575/1, 575/2, 575/3, 575/4, 583/3, 584/2, 585/3, 588/4, 590/2, 592/1, 593/1, 593/2 रकबा क्रमशः 0.050, 0.050, 0.255, 0.146, 0.101, 0.121, 0.060, 0.032, 0.032, 0.032, 0.032, 0.248, 0.794, 0.158, 0.402, 0.498, 1.044, 0.530, 0.530 हेक्टेयर, के औद्योगिक प्रयोजन हेतु परिवर्तित भूमि का लगान 63375.00 रु0 की दर से दिनांक 01/10/2023 से प्रारंभ होने वाले वर्ष से प्रतिवर्ष निम्नानुसार तहसीलदार राजनांदगांव को भुगतान करना होगा।

क्र0	चालान का मद	चालान की राशि
1	परिवर्तित लगान	63375.00
2	जनपद उपकर	31688.00
3	पर्यावरण उपकर	7130.00
4	विकास उपकर	7130.00
5	प्रीमियम	255750.00

- उपरोक्तानुसार राशि शासकीय कोषालय में जमा कर मूल चालान की प्रति आवेदक द्वारा प्रस्तुत किया गया है, जिसे वासिल बाकि नवीस शाखा, तहसील राजनांदगांव के द्वारा तहसील के सी-2 पंजी में दर्ज करने का टीप अंकित है। प्रकरण में धारा 59 (2) के तहत पुनर्कर निर्धारण निम्नांकित शर्तों के अधीन किया जाता है।



30/8

1. इसे भू-राजस्व संहिता की धारा 172(1) के तहत व्यपवर्तन अनुज्ञा नहीं माना जावे।
2. आवेदित भूमि पर किसी भी प्रकार के निर्माण अथवा विकास के पूर्व सर्व संबंधित विभाग से अनापत्ति प्राप्त करना आवेदक के अनिवार्य व बंधनकारी होगा।
3. आवेदक द्वारा लोक स्वास्थ्य, सुविधा, तथा सुरक्षा को बनाए रखेगा। आस-पास की शासकीय भूमि में अतिक्रमण नहीं किया जावेगा।
4. शासन के पुनर्कर निर्धारण संबंधी समस्त विधिक प्रावधानों का पालन करना आवेदक के लिए अनिवार्य होगा। शर्तों के अपालन की स्थिति में यह आदेश स्वमेव निरस्त माना जाएगा।
5. व्यपवर्तित भूमि नगरीय क्षेत्र में होने से संबंधित नगरीय निकाय से एवं ग्रामीण क्षेत्र में संबंधित ग्राम पंचायत से भवन अनुज्ञा प्राप्त कर अधिरोपित शर्तों के अधधीन व्यपवर्तित प्रयोजन हेतु उपयोग की अनुमति होगी।
6. आवेदित भूमि का व्यपवर्तित मद अनुसार उपयोग में प्रवेश हेतु राष्ट्रीय राजमार्ग तथा राजकीय राजमार्ग से सीधे रास्ते की अनुमति नहीं होगी।
7. व्यपवर्तित भूमि पर प्रवेश हेतु रास्ता मद के अतिरिक्त अन्य मद की शासकीय भूमि के उपयोग की स्थिति में पृथक से अनुमति आवश्यक होगी। अन्यथा व्यपवर्तन निरस्त माना जाएगा।
8. आवेदित भूमि को एक चक में बटांकित खसरा मानते हुए व्यपवर्तन स्वीकार किया जा रहा है। व्यपवर्तित भूमि को पुनः उप विभाजन किए जाने की स्थिति में व्यपवर्तन स्वमेव निरस्त माना जावेगा।
9. व्यपवर्तन उपरांत निर्धारित भू-राजस्व पर्यावरण एवं अधोसंरचना उपकर, पंचायत उपकर इत्यादि नियमित जमा नहीं किए जाने की स्थिति में किसी भी समय, सूचना उपरांत व्यपवर्तन निरस्त किया जा सकेगा।



अनुविभागीय अधिकारी (रा०)
राजनांदगांव

क०/2783/प्रवा०-3/अ०वि०/2024
प्रतिलिपि :-

राजनांदगांव, दिनांक 01/07/2024
08

1. तहसीलदार राजनांदगांव (वासिल बांकि नवीस शाखा) राजनांदगांव को आवश्यक कार्यवाही हेतु अग्रपिप्त।
2. आवेदक कल्याणी इस्पात लिमिटेड द्वारा अधिकृत दिनेश कुमार यादव पिता श्री कुलदीप सिंह यादव, निवासी एस० एच०-11, गार्डन ग्रूव, लालपुर, देवोपुरी, रायपुर, तहसील व जिला रायपुर (छत्तीसगढ़), प्रतिवर्ष देय रकम निर्धारित समय में जमा करना सुनिश्चित करें।

अनुविभागीय अधिकारी (रा०)
राजनांदगांव



कार्यालय कार्यपालन अभियंता

तांदुला जल संसाधन संभाग

जिला-दुर्ग (छ0ग0)

CG

CG

(E-mail :- cetwrdrg@cgwrd.in, Govt. ID- cetwrdrg-wrd@cg.gov.in)

(टेलीफोन नं.-0788-4036118)

ज्ञापन क्रमांक...7406.../तक/अभिमत/2024

दुर्ग, दिनांक 23/12/2024

प्रति,

✓ कल्याणी इस्पात लिमिटेड,

कार्यालय पता- प्रथम मंजिल, मकान नं. 117,

बिल्डिंग नं. N-18, सेक्टर-2, एस.बी.आई. ए.टी.एम. के पास,

अवंती विहार, रायपुर, जिला-रायपुर (छ.ग.) 492001

विषय:- अंजोरा जलाशय क. 1 के नहर (आर.बी.सी) में पुलिया निर्माण के संबंध में।

संदर्भ:- 1. आपका पत्र दिनांक 10.12.2024, प्राप्ति दिनांक 17.12.2024


2. अनु.अधि. जल संसा. उपसंभाग दुर्ग का पत्र क्र.-818/अ.वि.लि. दुर्ग दिनांक 20.12.2024

—000—

उपरोक्त विषयांतर्गत संदर्भित पत्र के संबंध में लेख है कि लघु सिंचाई योजना अंजोरा जलाशय क. 1 के आर.बी.सी. नहर की दोनों ओर इस्पात संयंत्र की भूमि है। कल्याणी इस्पात संयंत्र के द्वारा आवागमन के लिए नहर के ऊपर लगभग 19 मी. चौड़ा पुलिया निर्माण हेतु अनुमति चाही गई है, अनुविभागीय अधिकारी जल संसाधन उपसंभाग दुर्ग द्वारा स्थल निरीक्षण किया गया। निरीक्षण प्रतिवेदन में कल्याणी इस्पात संयंत्र द्वारा नहर की चौड़ाई 10 मी. को छोड़कर पियर निर्माण पश्चात् लाईनिंग नहर के स्थान पर 0.90 मी. X 0.80 मी. का RCC चैनल निर्माण प्रस्तावित किया है। प्रस्तावित कार्य के होने से नहर से सिंचाई करने में कोई कठिनाई नहीं होगी। अतः विभागीय मापदण्ड के अनुसार पुलिया निर्माण करने के लिए कल्याणी इस्पात संयंत्र को सशर्त अनुमति दी जा सकती है।

1. पुलिया निर्माण के दौरान नहर नाली के वाटर वे में किसी भी प्रकार का परिवर्तन न हों।
2. पुलिया निर्माण के दौरान नहर नाली में किसी भी प्रकार की टूट-फूट न हों।
3. पुलिया निर्माण के दौरान नहर नाली में जल प्रदाय के दौरान किसी भी प्रकार का अवरोध न हो।
4. पुलिया निर्माण के दौरान नहर में टूट-फूट हो जानें पर मरम्मत करने की जिम्मेदारी आपकी होगी।
5. पुलिया सार्वजनिक रूप से उपयोग हेतु रहेगा।
6. पुलिया पर विभाग का स्वामित्व बना रहेगा।
7. कार्य प्रारंभ के पूर्व अनुविभागीय अधिकारी, जल संसाधन उपसंभाग दुर्ग को लिखित सूचना देना होगा।
8. निर्माण कार्य संबंधित उपअभियंता के दिशा-निर्देश पर किया जावेगा।

सहपत्र:- ~~शून्य~~ एड नक्शा


कार्यपालन अभियंता
तांदुला जल संसाधन संभाग
दुर्ग (छ.ग.)

पृ0 क्रमांक/तक./अभिमत/2024


दुर्ग, दिनांक/12/2024

प्रतिलिपि:-


अनुविभागीय अधिकारी, जल संसाधन उपसंभाग दुर्ग को उनके पत्र क्रं. 818/अ.वि.लि./दुर्ग, दिनांक 20.12.2024 के संदर्भ में सूचनार्थ एवं आवश्यक कार्यवाही हेतु प्रेषित।

सहपत्र:- शून्य।



—सही—
कार्यपालन अभियंता
तांदुला जल संसाधन संभाग
दुर्ग (छ.ग.)



PLAN



SECTIONAL ELEVATION X-X'



SECTION AA'

Assistant Engineer
Tandula W.R. Division Durg (C.G.)

Assistant Engineer
Tandula W.R. Division Durg (C.G.)

Sub-Divisional Officer
Water Resources Sub-Division
Durg (C.G.)
Executive Engineer
Tandula W.R. Division Durg (C.G.)
Division Durg (Chhattisgarh)

CONCEPTUAL BRIDGE PLAN OF 1.2M WIDTH
CHANNEL CANAL AT KALYANI ISPAT Ltd.

KOPEDIH, RAJNANDGAON (C.G.)

NOTE -
1. DO NOT SCALE WORK TO WRITTEN
DIMENSIONS ONLY
2. IN CASE OF ANY DISCREPANCY, CONTACT
KANKARIYA CONSULTANTS
3. KANKARIYA CONSULTANTS WILL NOT TAKE
ANY LIABILITY IF ANY PART OF DRAWING IS NOT
FOLLOWED ON SITE

CLIENT NAME
KALYANI ISPAT

DRAWING NO.
ST/3

DESIGNED BY
A. KUSHAL KANKARIYA


CHECKED BY
Er. VIJAY KANKARIYA

DRAFTED BY
ADITI.K


PURPOSE
• FOR PROPOSAL
• FOR CONSTRUCTION




KANKARIYA CONSULTANTS
SHOP NO. 11, 12 FARISHTA COMPLEX
STATION ROAD DURG (C.G.)
Mob no.: 9329029988, 7000320943



PLAN



SECTIONAL ELEVATION X-X'



SECTION AA'

Assistant Engineer
Tandula W.R. Division Durg (C.G.)

Assistant Engineer
Tandula W.R. Division Durg (C.G.)

Sub-Divisional Officer
Water Resources Sub-Division
Durg (C.G.)
Executive Engineer
Tandula W.R. Division Durg (C.G.)
Division Durg (Chhattisgarh)

CONCEPTUAL BRIDGE PLAN OF 1.2M WIDTH
CHANNEL CANAL AT KALYANI ISPAT Ltd.

KOPEDIH, RAJNANDGAON (C.G.)

NOTE -
1. DO NOT SCALE WORK TO WRITTEN
DIMENSIONS ONLY
2. IN CASE OF ANY DISCREPANCY, CONTACT
KANKARIYA CONSULTANTS
3. KANKARIYA CONSULTANTS WILL NOT TAKE
ANY LIABILITY IF ANY PART OF DRAWING IS NOT
FOLLOWED ON SITE

CLIENT NAME
KALYANI ISPAT

DRAWING NO.
ST/3

DESIGNED BY
Ar. KUSHAL KANKARIYA

CHECKED BY
Er. VIJAY KANKARIYA

DRAFTED BY
ADIT.K

PURPOSE
• FOR PROPOSAL
• FOR CONSTRUCTION



KANKARIYA CONSULTANTS
SHOP NO. 11,12 FARISHTA COMPLEX
STATION ROAD DURG (C.G.)
Mob no.:- 9329029988, 7000320943



भारत सरकार
जल शक्ति मंत्रालय
जल संसाधन, नदी विकास
और गंगा संरक्षण विभाग
केन्द्रीय भूमि जल प्राधिकरण
Government of India
Ministry of Jal Shakti
Department of Water Resources,
River Development & Ganga Rejuvenation
Central Ground Water Authority

**MODIFICATION REQUEST
(EXPANSION)
(भूजल निकासी हेतु अनापत्ति प्रमाण पत्र)
NO OBJECTION CERTIFICATE (NOC) FOR GROUND WATER ABSTRACTION**

Project Name:	Kalyani Ispat Limited		
Project Address:	Villages- Kopedeesh, Teh. And Distt-rajnandgaon		
Village:	Kopedeesh	Block:	Rajnandgaon
District:	Rajnandgaon	State:	Chhattisgarh
Pin Code:			
Communication Address:	House No.- 117, Building No – N-18, First Floor, Sector-2, Near Sbi Atm, Avanti Vihar, Raipur, Dharsiwa, Raipur, Chhattisgarh - 492001		
Address of CGWB Regional Office :	Central Ground Water Board North Central Chhattisgarh, 2nd Floor, Lk Corporate And Logistic Park, Dhamtari Road, Nh-30, Dumartarai, Raipur, Chhattisgarh - 492015		

1. NOC No.:	CGWA/NOC/IND/EXP/2025/156	2. Date of Issuance	04/02/2025
3. Application No.:	21-4/11553/CT/IND/2024	4. Category: (GWRE 2024)	Semi Critical
5. Project Status:	New Project	6. NOC Type:	Expansion
7. Valid from:	31/01/2025	8. Valid up to:	16/10/2027
9. Ground Water Abstraction Permitted:			

Fresh Water		Saline Water		Dewatering		Total	
m ³ /day	m ³ /year	m ³ /day	m ³ /year	m ³ /day	m ³ /year	m ³ /day	m ³ /year
495.00	180675.00						

10. Details of ground water abstraction /Dewatering structures

	Total Existing No						Total Proposed No					
	DW	DCB	BW	TW	MP	MPu	DW	DCB	BW	TW	MP	MPu
Abstraction Structure*	0	0	2	0	0	0	0	0	8	0	0	0

*DW- Dug Well; DCB-Dug-cum-Bore Well; BW-Bore Well; TW-Tube Well; MP-Mine Pit;MPu-Mine Pumps

11. Ground Water Abstraction/Restoration Charges paid (Rs.):	547025.00			
12. Environment Compensation (if applicable) paid (Rs.):	0.00			
13. Number of Piezometers(Observation wells) to be constructed/ monitored & Monitoring mechanism.	No. of Piezometers	Monitoring Mechanism		
		Manual	DWLR**	DWLR With Telemetry
**DWLR - Digital Water Level Recorder	1	0	1	0

18/11, जामनगर हाउस, मानसिंह रोड, नई दिल्ली - 110011 / 18/11, Jamnagar House, Mansingh Road, New Delhi-110011
Phone: (011) 23383561 Fax: 23382051, 23386743
Website: cgwa-noc.gov.in

पानी बचाये - जीवन बचाये
SAVE WATER - SAVE LIFE

Validity of this NOC shall be subject to compliance of the following conditions:

Mandatory conditions:

- 1) Installation of tamper proof digital water flow meter with telemetry on all the abstraction structure(s) shall be mandatory for all users seeking No Objection Certificate and intimation regarding their installation shall be communicated to the CGWA within 30 days of grant of No Objection Certificate.
- 2) Proponents shall mandatorily get water flow meter calibrated from an authorized agency once in a year.
- 3) Construction of purpose-built observation wells (piezometers) for ground water level monitoring shall be mandatory as per Section 14 of Guidelines. Water level data shall be made available to CGWA through web portal. Detailed guidelines for construction of piezometers are given in Annexure-II of the guidelines.
- 4) Proponents shall monitor quality of ground water from the abstraction structure(s) once in a year. Water samples from bore wells/ tube wells / dug wells shall be collected during April/May every year and analysed in NABL accredited laboratories for basic parameters (cations and anions), heavy metals, pesticides/ organic compounds etc. Water quality data shall be made available to CGWA through the web portal.
- 5) In case of mining projects, additional key wells shall be established in consultation with the Regional Director, CGWB for ground water level monitoring four (4) times a year (January, May, August and November) in core as well as buffer zones of the mine.
- 6) In case of mining project the firm shall submit water quality report of mine discharge/ seepage from Govt. approved/ NABL accredited lab.
- 7) The firm shall report compliance of the NOC conditions online in the website (www.cgwa-noc.gov.in) within one year from the date of issue of this NOC.
- 8) Industries abstracting ground water in excess of 100 m³/d shall undertake annual water audit through certified auditors and submit audit reports within three months of completion of the same to CGWA. All such industries shall be required to reduce their ground water use by at least 20% over the next three years through appropriate means.
- 9) Application for renewal can be submitted online from 90 days before the expiry of NOC. Ground water withdrawal, if any, after expiry of NOC shall be illegal & liable for legal action as per provisions of Environment (Protection) Act, 1986.
- 10) This NOC is subject to prevailing Central/State Government rules/laws/norms or Court orders related to construction of tube well/ground water abstraction structure / recharge or conservation structure/discharge of effluents or any such matter as applicable.

General conditions:

- 11) No additional ground water abstraction and/or de-watering structures shall be constructed for this purpose without prior approval of the Central Ground Water Authority (CGWA).
- 12) The proponent shall seek prior permission from CGWA for any increase in quantum of groundwater abstraction (more than that permitted in NOC for specific period).
- 13) Proponents shall install roof top rain water harvesting in the premise as per the existing building bye laws in the premise.
- 14) The project proponent shall take all necessary measures to prevent contamination of ground water in the premises failing which the firm shall be responsible for any consequences arising thereupon.
- 15) In case of industries that are likely to contaminate the ground water, no recharge measures shall be taken up by the firm inside the plant premises. The runoff generated from the rooftop shall be stored and put to beneficial use by the firm.
- 16) Wherever feasible, requirement of water for greenbelt (horticulture) shall be met from recycled / treated waste water.
- 17) Wherever the NOC is for abstraction of saline water and the existing wells (s) is /are yielding fresh water, the same shall be sealed and new tubewell(s) tapping saline water zone shall be constructed within 3 months of the issuance of NOC. The firm shall also ensure safe disposal of saline residue, if any.
- 18) Unexpected variations in inflow of ground water into the mine pit, if any, shall be reported to the concerned Regional Director, Central Ground Water Board.
- 19) In case of violation of any NOC conditions, the applicant shall be liable to pay the penalties as per Section 16 of Guidelines.
- 20) This NOC does not absolve the proponents of their obligation / requirement to obtain other statutory and administrative clearances from appropriate authorities.
- 21) The issue of this NOC does not imply that other statutory / administrative clearances shall be granted to the project by the concerned authorities. Such authorities would consider the project on merits and take decisions independently of the NOC.
- 22) In case of change of ownership, new owner of the industry will have to apply for incorporation of necessary changes in the No Objection Certificate with documentary proof within 60 days of taking over possession of the premises.
- 23) This NOC is being issued without any prejudice to the directions of the Hon'ble NGT/court orders in cases related to ground water or any other related matters.
- 24) Proponents, who have installed/constructed artificial recharge structures in compliance of the NOC granted to them previously and have availed rebate of upto 50% (fifty percent) in the ground water abstraction charges/ground water restoration charges, shall continue to regularly maintain artificial recharge structures.
- 25) Industries which are likely to cause ground water pollution e.g. Tanning, Slaughter Houses, Dye, Chemical/ Petrochemical, Coal washeries, pharmaceutical, other hazardous units etc. (as per CPCB list) need to undertake necessary well head protection measures to ensure prevention of ground water pollution as per Annexure III of the guidelines.
- 26) In case of new infrastructure projects having ground water abstraction of more than 20 m³/day, the firm/entity shall ensure implementation of dual water supply system in the projects.
- 27) In case of infrastructure projects, paved/parking area must be covered with interlocking/perforated tiles or other suitable measures to ensure groundwater infiltration/harvesting.
- 28) In case of coal and other base metal mining projects, the project proponent shall use the advance dewatering technology (by construction of series of dewatering abstraction structures) to avoid contamination of surface water.
- 29) The NOC issued is conditional subject to the conditions mentioned in the Public notice dated 27.01.2021 failing which penalty/EC/cancellation of NOC shall be imposed as the case may be.
- 30) This NOC is issued subject to the clearance of Expert Appraisal Committee (EAC) (if applicable).
- 31) In the self-compliance report, the PP shall submit details of Drilling Agency/ Agencies, which has/ have constructed BW(s)/ TW(s) along with undertaking to the effect that all necessary measures have been taken as per directions of Hon'ble Supreme Court provided in Annexure-VII of guidelines dated 24.09.2020 in respect of abandoned/ failed BW(s)/ TW(s)/Piezometer(s), if any. The PP is advised to engage registered drilling agency/ agencies. In the event of any mishap/ unfortunate incident due to negligence in taking measures for prevention of accident due to falling in Bore Well, both PP and concerned drilling agency shall jointly be held responsible and penal action as per extant Government rules shall be taken.

(Non-compliance of the conditions mentioned above is likely to result in the cancellation of NOC and legal action against the proponent.)

18/11, जामनगर हाउस, मानसिंह रोड, नई दिल्ली - 110011 / 18/11, Jamnagar House, Mansingh Road, New Delhi-110011

Phone: (011) 23383561 Fax: 23382051, 23386743

Website: cgwa-noc.gov.in

पानी बचाये – जीवन बचाये
SAVE WATER - SAVE LIFE

CENTRAL GROUND WATER AUTHORITY

Department of Water Resources, River Development and Ganga Rejuvenation
Ministry of Jal Shakti, Govt. of India

Receipt

(As per the guideline Gazette Notification S.O. 3281(E) regarding the New Guidelines dated 24.09.2020 of CGWA, MoJS, Govt. of India)
<https://cgwa-noc.gov.in>

Application No.: 21-4/11553/CT/IND/2024

Name of Firm: KALYANISRAT LIMITED

S	Description	Amount (Rs.)
N		
1.	Application Processing Fee	5000.00
2.	Ground Water Abstraction / Restoration charges	547025.00
3.	Environmental Compensation Charges (ECRGW) (Date From to) Days-	
4.	Penalty for non-Compliance of NOC conditions Condition to be mentioned	
	Rs. Rupees Five Lakh Fifty Two Thousand Twenty Five Only	552025.00

This is an system generated invoice, hence, does not require ink signed.

Term and conditions:

- All disputes are subject to Delhi Jurisdiction.
- Any complaint in regard to the rates will not be entertained

Member-Secretary
CGWA, New Delhi

18/11, जामनगर हाउस, मानसिंह रोड, नई दिल्ली - 110011 / 18/11, Jamnagar House, Mansingh Road, New Delhi-110011

Phone: (011) 23383561 Fax: 23382051, 23386743

Website: cgwa-noc.gov.in

पानी बचाये - जीवन बचाये
SAVE WATER - SAVE LIFE



छत्तीसगढ़ स्टेट इण्डस्ट्रियल डेवलपमेंट कॉर्पोरेशन लिमिटेड

(छत्तीसगढ़ शासन का एक उपक्रम)

(ISO 9001:2015 Certified)

प्रथम तल, उद्योग भवन, रिंग रोड नं. 01, तेलीबांधा, रायपुर, (छ.ग.) 492006

CIN : U45203CT1981SG001853, PAN : AABCM6288N, GST Regn No. : 22AABCM6288NSZY

दूरभाष : कार्यालय- 0771-6621000, फ़ैक्स: 0771-2583794

Website: www.csidc.in Email address: csidc.cg@nic.in, csidc_raipur@yahoo.com

क्रमांक/सीएसआईडीसी/सं-04/2022-23/ 4392

रायपुर, दिनांक 10/08/2022

प्रति,

✓ मेसर्स कल्याणी इस्पात लिमिटेड,
439, चतुर्थ तल, मेग्नेटो मॉल,
जी.ई. रोड, लामांडी, रायपुर (छ.ग.)
पिनकोड:- 492005
Email Id:- info@kalyaniindia.com

Regd


विषय:- ग्राम-फूलझर-नवागाँव जिला-राजनांदगाँव में स्थापित हो रहे इकाई हेतु जल प्रदाय किए जाने के संबंध में।

संदर्भ:- आपका आवेदन क्र. केआईएल/वॉटर/2022-23/14 दिनांक 14.07.2022.

विषयांतर्गत संदर्भित पत्र के माध्यम से आपके द्वारा ग्राम-फूलझर-नवागाँव जिला-राजनांदगाँव में प्रस्तावित इकाई हेतु औद्योगिक क्षेत्र बोर्ड जल प्रदाय योजना से प्रतिदिन 60.00 लाख लीटर जल प्रदाय हेतु 02 चरणों में प्रथम चरण में 30.00 लाख लीटर वर्ष 2024 तक एवं द्वितीय चरण में 30.00 लाख लीटर वर्ष 2024 के बाद माँग की गई है। वर्तमान में जल संसाधन विभाग से प्रथम चरण का 15.00 एम.एल.डी. हेतु जल अनुबंध निष्पादित किया गया है। अतः आपके प्रथम चरण की 30.00 लाख लीटर जल माँग को सीएसआईडीसी, वाणिज्य एवं उद्योग विभाग, जल संसाधन विभाग एवं अन्य संबंधित विभागों के प्रचलित नियमों एवं प्रावधान के अधीन अनुमति/अनापत्ति प्राप्त करने की शर्त के साथ जल उपलब्धता के आधार पर उपलब्ध कराए जाने की सहमति एतद् द्वारा दी जाती है। इस संबंध में समय-समय पर छत्तीसगढ़ शासन द्वारा जारी होने वाले निर्देश एवं नियम बंधनकारी होंगे। इस हेतु नियम एवं शर्तें पृथक से अवगत कराई जाएगी। जल आपूर्ति के संबंध में इस निगम का सर्वाधिकार सुरक्षित रहेगा।

आपके द्वितीय चरण वर्ष 2024 के बाद 30.00 लाख लीटर जल माँग को इस निगम द्वारा जल संसाधन विभाग से द्वितीय चरण का जल आबंटन 15.00 एम.एल.डी. का प्रस्ताव स्वीकृत होने के पश्चात् दिया जाना संभव हो सकेगा।

सधन्यवाद,


कार्यपालक संचालक

पृ.क्रमांक/सीएसआईडीसी/सं-04/2022-23/
प्रतिलिपि :-

रायपुर, दिनांक /08/2022

1. कार्यपालन अभियंता, सीएसआईडीसी, संभाग-04, रायपुर की ओर सूचनार्थ।
2. सहायक अभियंता, सीएसआईडीसी, संभाग- 04, रायपुर की ओर सूचनार्थ।

कार्यपालक संचालक



CENTRE FOR ENVOTECH AND MANAGEMENT CONSULTANCY PVT. LTD. (LAB DIVISION)

An ISO 9001:2015, ISO 45001:2018 & ISO 14001:2015 Certified Company,

Plot No. 800/1274, Johal, Pahal, Bhubaneswar-752101, E-mail: cemclab@yahoo.in. Mobile: 9439050689

Report No. - CEMC/RM/300525/A1

Issued Date-30.05.2025

AMBIENT AIR QUALITY MONITORING REPORT

Name & Address of the Client	M/s Kalyani Ispat Ltd., Kh No.- 585/1, Kopedeeh, Rajnandgaon, Chhatisgarh
Reference No.	CEMC-300525A1
Nature of Sampling	Ambient Air Sample
Sampling By	Mr. Bhakta Hari Das
Instrument Used	Respirable Dust Sampler, Fine Particulate Sampler, CO Meter and Gaseous Attachment
Location of Sampling	AAQM St.-1 (WHRB)
Sampling Date	21.05.2025 to 22.05.2025

ANALYSIS RESULT

Sl. No.	Parameters	Result	Standard as per NAAQ*	Methods of Analysis
1	Particulate Matter (PM ₁₀) µg/m ³	70.8	100	IS: 5182 (Part-23)
2	Particulate Matter (PM _{2.5}) µg/m ³	34.4	60	IS: 5182 (Part-24)
3	Sulphur Dioxide (SO ₂) µg/m ³	9.2	80	IS: 5182 (Part-2)
4	Nitrogen Oxides (NO _x) µg/m ³	14.4	80	IS: 5182 (Part-6)
5	Carbon Monoxide (CO) mg/m ³	0.23	4.0	IS: 5182 (Part-10)
6	Ozone (O ₃) µg/m ³	<10	100	IS: 5182 (Part-9)
7	Ammonia (NH ₃) µg/m ³	<20	400	IS: 5182 (Part-25)
8	Lead (Pb) µg/m ³	<0.05	1.0	IS: 5182 (Part-22)
9	Nickel (Ni) ng/m ³	<3.2	20	IS: 5182 (Part-26)
10	Arsenic (As) ng/m ³	<0.1	6	As per CPCB method followed by AAS
11	Benzene (C ₆ H ₆) µg/m ³	<5	5	IS: 5182 (Part-11)
12	Benzo(a)Pyrene (BaP) ng/m ³	<1	1	IS: 5182 (Part-12)

*NAAQS (National Ambient Air Quality Standard as per 18th Nov, 2009 Gatt. Notification)

End of Report

D. Das
Authorized Signatory

Notes:

- The results relate only to the sample tested
- This Test Report shall not be reproduced wholly or in part without prior written consent of the laboratory.
- The samples received shall be destroyed after two weeks from the date of issue of the Test Report unless specified otherwise.
- This Test Report shall not be used in any advertising media or as evidence in the court of Law without prior written consent of the laboratory.




CEMC PVT. LTD., NABET(QCI) Accredited Category 'A' Consultant Organization.

Regd. Office: Plot No. 522/3458, Pahal, Bhubaneswar-752101, Odisha, India, Mobile: 9861032826

E-mail- cemc_consultancy@yahoo.co.in, cemc122@gmail.com, website: www.cemcpl.com

Deals with Environmental Studies (EIA & EMP), Monitoring, Forest Diversion Planning, DPR, Wildlife Management Plan, Hazardous & Safety Studies, RS & GIS, Hydrological Studies, Socio-economic Studies, DGPS & ETS Survey.



CENTRE FOR ENVOTECH AND MANAGEMENT CONSULTANCY PVT. LTD. (LAB DIVISION)

An ISO 9001:2015, ISO 45001:2018 & ISO 14001:2015 Certified Company,

Plot No. 800/1274, Johal, Pahal, Bhubaneswar-752101, E-mail: cemclub@yahoo.in. Mobile: 9439050689

Report No. - CEMC/RM/300525/A2

Issued Date-30.05.2025

AMBIENT AIR QUALITY MONITORING REPORT

Name & Address of the Client	M/s Kalyani Ispat Ltd., Kh No.- 585/1, Kopedeoh, Rajnandgaon, Chhatisgarh
Reference No.	CEMC-300525A2
Nature of Sampling	Ambient Air Sample
Sampling By	Mr. Bhakta Hari Das
Instrument Used	Respirable Dust Sampler, Fine Particulate Sampler, CO Meter and Gaseous Attachment
Location of Sampling	AAQMSt-2 (Main Gate)
Sampling Date	21.05.2025 to 22.05.2025

ANALYSIS RESULT

Sl. No.	Parameters	Result	Standard as per NAAQ*	Methods of Analysis
1	Particulate Matter (PM ₁₀) µg/m ³	77.3	100	IS: 5182 (Part-23)
2	Particulate Matter (PM _{2.5}) µg/m ³	39.5	60	IS: 5182 (Part-24)
3	Sulphur Dioxide (SO ₂) µg/m ³	15.2	80	IS: 5182 (Part-2)
4	Nitrogen Oxides (NO _x) µg/m ³	19.4	80	IS: 5182 (Part-6)
5	Carbon Monoxide (CO) mg/m ³	0.3	4.0	IS: 5182 (Part-10)
6	Ozone (O ₃) µg/m ³	<10	100	IS: 5182 (Part-9)
7	Ammonia (NH ₃) µg/m ³	<20	400	IS: 5182 (Part-25)
8	Lead (Pb) µg/m ³	<0.05	1.0	IS: 5182 (Part-22)
9	Nickel (Ni) ng/m ³	<3.2	20	IS: 5182 (Part-26)
10	Arsenic (As) ng/m ³	<0.1	6	As per CPCB method followed by AAS
11	Benzene (C ₆ H ₆) µg/m ³	<5	5	IS: 5182 (Part-11)
12	Benzo(a)Pyrene (BaP) ng/m ³	<1	1	IS: 5182 (Part-12)

*NAAQS (National Ambient Air Quality Standard as per 18th Nov, 2009 Gatt. Notification)

End of Report

B. P. Das
Authorized Signatory

Seal of Laboratory

Notes:


- The results relate only to the sample tested.
- This Test Report shall not be reproduced wholly or in part without prior written consent of the laboratory.
- The samples received shall be destroyed after two weeks from the date of issue of the Test Report unless specified otherwise.
- This Test Report shall not be used in any advertising media or as evidence in the court of Law without prior written consent of the laboratory.

CEMC PVT. LTD., NABET(QCI) Accredited Category 'A' Consultant Organization.

Regd. Office: Plot No. 522/3458, Pahal, Bhubaneswar-752101, Odisha, India, Mobile: 9861032826

E-mail- cemc_consultancy@yahoo.co.in, cemc122@gmail.com, website: www.cemcpl.com

Deals with Environmental Studies (EIA & EMP), Monitoring, Forest Diversion Planning, DPR, Wildlife Management Plan, Hazardous & Safety Studies, RS & GIS, Hydrological Studies, Socio-economic Studies, DGPS & ETS Survey.



CENTRE FOR ENVOTECH AND MANAGEMENT CONSULTANCY PVT. LTD. (LAB DIVISION)

An ISO 9001:2015, ISO 45001:2018 & ISO 14001:2015 Certified Company,

Plot No. 800/1274, Johal, Pahal, Bhubaneswar-752101, E-mail: cemclab@yahoo.in. Mobile: 9439050689

Report No. - CEMC/RM/300525/A3

Issued Date-30.05.2025

AMBIENT AIR QUALITY MONITORING REPORT

Name & Address of the Client	M/s Kalyani Ispat Ltd., Kh No.- 585/1, Kopedeeh, Rajnandgaon, Chhatisgarh
Reference No.	CEMC-300525A3
Nature of Sampling	Ambient Air Sample
Sampling By	Mr. Bhakta Hari Das
Instrument Used	Respirable Dust Sampler, Fine Particulate Sampler, CO Meter and Gaseous Attachment
Location of Sampling	AAQMSt.-3 (Gate-2)
Sampling Date	21.05.2025 to 22.05.2025

ANALYSIS RESULT

Sl. No.	Parameters	Result	Standard as per NAAQ*	Methods of Analysis
1	Particulate Matter (PM ₁₀) µg/m ³	71.6	100	IS: 5182 (Part-23)
2	Particulate Matter (PM _{2.5}) µg/m ³	36.5	60	IS: 5182 (Part-24)
3	Sulphur Dioxide (SO ₂) µg/m ³	10.7	80	IS: 5182 (Part-2)
4	Nitrogen Oxides (NO _x) µg/m ³	<9	80	IS: 5182 (Part-6)
5	Carbon Monoxide (CO) mg/m ³	<0.05	4.0	IS: 5182 (Part-10)
6	Ozone (O ₃) µg/m ³	<10	100	IS: 5182 (Part-9)
7	Ammonia (NH ₃) µg/m ³	<20	400	IS: 5182 (Part-25)
8	Lead (Pb) µg/m ³	<0.05	1.0	IS: 5182 (Part-22)
9	Nickel (Ni) ng/m ³	<3.2	20	IS: 5182 (Part-26)
10	Arsenic (As) ng/m ³	<0.1	6	As per CPCB method followed by AAS
11	Benzene (C ₆ H ₆) µg/m ³	<5	5	IS: 5182 (Part-11)
12	Benzo(a)Pyrene (BaP) ng/m ³	<1	1	IS: 5182 (Part-12)

*NAAQS (National Ambient Air Quality Standard as per 18th Nov, 2009 Gatt. Notification)

End of Report

BPDal
Authorized Signatory

Seal of Laboratory

Notes:

- The results relate only to the sample tested.
- This Test Report shall not be reproduced wholly or in part without prior written consent of the laboratory.
- The samples received shall be destroyed after two weeks from the date of issue of the Test Report unless specified otherwise.
- This Test Report shall not be used in any advertising media or as evidence in the court of Law without prior written consent of the laboratory.

CEMC PVT. LTD., NABET(QCI) Accredited Category 'A' Consultant Organization.

Regd. Office: Plot No. 522/3458, Pahal, Bhubaneswar-752101, Odisha, India, Mobile: 9861032826

E-mail- cemc_consultancy@yahoo.co.in, cemc122@gmail.com, website: www.cemcpl.com

Deals with Environmental Studies (EIA & EMP), Monitoring, Forest Diversion Planning, DPR, Wildlife Management Plan, Hazardous & Safety Studies, RS & GIS, Hydrological Studies, Socio-economic Studies, DGPS & ETS Survey.



CENTRE FOR ENVOTECH AND MANAGEMENT CONSULTANCY PVT. LTD. (LAB DIVISION)

An ISO 9001:2015, ISO 45001:2018 & ISO 14001:2015 Certified Company,

Plot No. 800/1274, Johal, Pahal, Bhubaneswar-752101, E-mail: cemclab@yahoo.in. Mobile: 9439050689

Report No. - CEMC/RM/300525/A4

Issued Date-30.05.2025

AMBIENT AIR QUALITY MONITORING REPORT

Name & Address of the Client	M/s Kalyani Ispat Ltd., Kh No.- 585/1, Kopedeeh, Rajnandgaon, Chhatisgarh
Reference No.	CEMC-300525A4
Nature of Sampling	Ambient Air Sample
Sampling By	Mr. Bhakta Hari Das
Instrument Used	Respirable Dust Sampler, Fine Particulate Sampler, CO Meter and Gaseous Attachment
Location of Sampling	AAQMSt.-4(Pellet Hurtment)
Sampling Date	21.05.2025 to 22.05.2025

ANALYSIS RESULT

Sl. No.	Parameters	Result	Standard as per NAAQ*	Methods of Analysis
1	Particulate Matter (PM ₁₀) µg/m ³	69.6	100	IS: 5182 (Part-23)
2	Particulate Matter (PM _{2.5}) µg/m ³	33.8	60	IS: 5182 (Part-24)
3	Sulphur Dioxide (SO ₂) µg/m ³	8.2	80	IS: 5182 (Part-2)
4	Nitrogen Oxides (NO _x) µg/m ³	11.4	80	IS: 5182 (Part-6)
5	Carbon Monoxide (CO) mg/m ³	0.14	4.0	IS: 5182 (Part-10)
6	Ozone (O ₃) µg/m ³	<10	100	IS: 5182 (Part-9)
7	Ammonia (NH ₃) µg/m ³	<20	400	IS: 5182 (Part-25)
8	Lead (Pb) µg/m ³	<0.05	1.0	IS: 5182 (Part-22)
9	Nickel (Ni) ng/m ³	<3.2	20	IS: 5182 (Part-26)
10	Arsenic (As) ng/m ³	<0.1	6	As per CPCB method followed by AAS
11	Benzene (C ₆ H ₆) µg/m ³	<5	5	IS: 5182 (Part-11)
12	Benzo(a)Pyrene (BaP) ng/m ³	<1	1	IS: 5182 (Part-12)


*NAAQS (National Ambient Air Quality Standard as per 18th Nov, 2009 Gatt. Notification)

End of Report

B.P.Das
Authorized Signatory

Notes:

- The results relate only to the sample tested.
- This Test Report shall not be reproduced wholly or in part without prior written consent of the laboratory.
- The samples received shall be destroyed after two weeks from the date of issue of the Test Report unless specified otherwise.
- This Test Report shall not be used in any advertising media or as evidence in the court of Law without prior written consent of the laboratory.



CEMC PVT. LTD., NABET(QCI) Accredited Category 'A' Consultant Organization.

Regd. Office: Plot No. 522/3458, Pahal, Bhubaneswar-752101, Odisha, India, Mobile: 9861032826

E-mail- cemc_consultancy@yahoo.co.in, cemc122@gmail.com, website: www.cemcpl.com

Deals with Environmental Studies (EIA & EMP), Monitoring, Forest Diversion Planning, DPR, Wildlife Management Plan, Hazardous & Safety Studies, RS & GIS, Hydrological Studies, Socio-economic Studies, DGPS & ETS Survey.



CENTRE FOR ENVOTECH AND MANAGEMENT CONSULTANCY PVT. LTD. (LAB DIVISION)

An ISO 9001:2015, ISO 45001:2018 & ISO 14001:2015 Certified Company,

Plot No. 800/1274, Johal, Pahal, Bhubaneswar-752101, E-mail: cemclab@yahoo.in. Mobile: 9439050689

Report No. - CEMC/RM/300525/F1

Issued Date-30.05.2025

FUGITIVE MONITORING REPORT

Name & Address of the Client	M/s Kalyani Ispat Ltd., Kh No.- 585/1, Kopedeeh, Rajnandgaon, Chhatisgarh
Reference No.	CEMC-300525F1
Nature of Sampling	Fugitive Air Sample
Sampling By	Mr. Bhakta Hari Das
Instrument Used	Respirable Dust Sampler
Location of Sampling	Near PPP Cool Shed
Sampling Date	22.05.2025

ANALYSIS RESULT

Sl. No.	Items	Unit	Result	Testing Method
01	Suspended Particulate Matter (SPM)	$\mu\text{g}/\text{m}^3$	241	IS: 5182 (Part-4)

N.B. Standard as per Environment (Protection Act) 3rd Amendment Rules-2012 by MoEF & CC. 2000 $\mu\text{g}/\text{m}^3$ at 10mtr distance from the Source.

End of Report

BPDAS
Authorized Signatory

Seal of Laboratory
Laboratory

Notes:


- The results relate only to the sample tested.
- This Test Report shall not be reproduced wholly or in part without prior written consent of the laboratory.
- The samples received shall be destroyed after two weeks from the date of issue of the Test Report unless specified otherwise.
- This Test Report shall not be used in any advertising media or as evidence in the court of Law without prior written consent of the laboratory.

CEMC PVT. LTD., NABET(QCI) Accredited Category 'A' Consultant Organization.

Regd. Office: Plot No. 522/3458, Pahal, Bhubaneswar-752101, Odisha, India, Mobile: 9861032826

E-mail- cemc_consultancy@yahoo.co.in, cemc122@gmail.com, website: www.cemcpl.com

Deals with Environmental Studies (EIA & EMP), Monitoring, Forest Diversion Planning, DPR, Wildlife Management Plan, Hazardous & Safety Studies, RS & GIS, Hydrological Studies, Socio-economic Studies, DGPS & ETS Survey.



CENTRE FOR ENVOTECH AND MANAGEMENT CONSULTANCY PVT. LTD. (LAB DIVISION)

An ISO 9001:2015, ISO 45001:2018 & ISO 14001:2015 Certified Company,
Plot No. 800/1274, Johal, Pahal, Bhubaneswar-752101, E-mail: cemclab@yahoo.in. Mobile: 9439050689

Report No. - CEMC/RM/300525/F2

Issued Date-30.05.2025

FUGITIVE MONITORING REPORT

Name & Address of the Client	M/s Kalyani Ispat Ltd., Kh No.- 585/1, Kopedeeh, Rajnandgaon, Chhatisgarh
Reference No.	CEMC-300525F2
Nature of Sampling	Fugitive Air Sample
Sampling By	Mr. Bhakta Hari Das
Instrument Used	Respirable Dust Sampler
Location of Sampling	Near S.F Yard
Sampling Date	22.05.2025

ANALYSIS RESULT

Sl. No.	Items	Unit	Result	Testing Method
01	Suspended Particulate Matter (SPM)	$\mu\text{g}/\text{m}^3$	312	IS: 5182(Part-4)


N.B. Standard as per Environment (Protection Act) 3rd Amendment Rules-2012 by MoEF & CC. 2000 $\mu\text{g}/\text{m}^3$ at 10ms distance from the Source.

End of Report


Authorized Signatory

Notes:

- The results relate only to the sample tested.
- This Test Report shall not be reproduced wholly or in part without prior written consent of the laboratory.
- The samples received shall be destroyed after two weeks from the date of issue of the Test Report unless specified otherwise.
- This Test Report shall not be used in any advertising media or as evidence in the court of Law without prior written consent of the laboratory.




CEMC PVT. LTD., NABET(QCI) Accredited Category 'A' Consultant Organization.

Regd. Office: Plot No. 522/3458, Pahal, Bhubaneswar-752101, Odisha, India, Mobile: 9861032826

E-mail- cemc_consultancy@yahoo.co.in, cemc122@gmail.com, website: www.cemcpl.com

Deals with Environmental Studies (EIA & EMP), Monitoring, Forest Diversion Planning, DPR, Wildlife Management Plan, Hazardous & Safety Studies, RS & GIS, Hydrological Studies, Socio-economic Studies, DGPS & ETS Survey.



CENTRE FOR ENVOTECH AND MANAGEMENT CONSULTANCY PVT. LTD. (LAB DIVISION)

An ISO 9001:2015, ISO 45001:2018 & ISO 14001:2015 Certified Company,

Plot No. 800/1274, Johal, Pahal, Bhubaneswar-752101, E-mail: cemclab@yahoo.in. Mobile: 9439050689

Report No. - CEMC/RM/300525/F3

Issued Date-30.05.2025

FUGITIVE MONITORING REPORT

Name & Address of the Client	M/s Kalyani Ispat Ltd., Kh No.- 585/1, Kopedeeh, Rajnandgaon, Chhatisgarh
Reference No.	CEMC-300525F3
Nature of Sampling	Fugitive Air Sample
Sampling By	Mr. Bhakta Hari Das
Instrument Used	Respirable Dust Sampler
Location of Sampling	Near DRI
Sampling Date	22.05.2025


ANALYSIS RESULT

Sl. No.	Items	Unit	Result	Testing Method
01	Suspended Particulate Matter (SPM)	$\mu\text{g}/\text{m}^3$	378	IS: 5182 (Part-4)

N.B. Standard as per Environment (Protection Act) 3rd Amendment Rules-2012 by MoEF & CC. 2000 $\mu\text{g}/\text{m}^3$ at 10ms distance from the Source.

End of Report


Authorized Signatory
Notes:




- The results relate only to the sample tested.
- This Test Report shall not be reproduced wholly or in part without prior written consent of the laboratory.
- The samples received shall be destroyed after two weeks from the date of issue of the Test Report unless specified otherwise.
- This Test Report shall not be used in any advertising media or as evidence in the court of Law without prior written consent of the laboratory.

CEMC PVT. LTD., NABET(QCI) Accredited Category 'A' Consultant Organization.

Regd. Office: Plot No. 522/3458, Pahal, Bhubaneswar-752101, Odisha, India, Mobile: 9861032826

E-mail- cemc_consultancy@yahoo.co.in, cemc122@gmail.com, website: www.cemcpl.com

Deals with Environmental Studies (EIA & EMP), Monitoring, Forest Diversion Planning, DPR, Wildlife Management Plan, Hazardous & Safety Studies, RS & GIS, Hydrological Studies, Socio-economic Studies, DGPS & ETS Survey.



CENTRE FOR ENVOTECH AND MANAGEMENT CONSULTANCY PVT. LTD. (LAB DIVISION)

An ISO 9001:2015, ISO 45001:2018 & ISO 14001:2015 Certified Company,
Plot No. 800/1274, Johal, Pahal, Bhubaneswar-752101, E-mail: cemclab@yahoo.in. Mobile: 9439050689

Report No. - CEMC/RM/300525/F4

Issued Date-30.05.2025

FUGITIVE MONITORING REPORT

Name & Address of the Client	M/s Kalyani Ispat Ltd., Kh No.- 585/1, Kopedeeh, Rajnandgaon, Chhatisgarh
Reference No.	CEMC-300525F4
Nature of Sampling	Fugitive Air Sample
Sampling By	Mr. Bhakta Hari Das
Instrument Used	Respirable Dust Sampler
Location of Sampling	Near Pellet Plant
Sampling Date	22.05.2025

ANALYSIS RESULT

Sl. No.	Items	Unit	Result	Testing Method
01	Suspended Particulate Matter (SPM)	$\mu\text{g}/\text{m}^3$	351	IS: 5182 (Part-4)


N.B. Standard as per Environment (Protection Act) 3rd Amendment Rules-2012 by MoEF & CC. 2000 $\mu\text{g}/\text{m}^3$ at 10ms distance from the Source.

End of Report


Authorized Signatory

Notes:

- The results relate only to the sample tested.
- This Test Report shall not be reproduced wholly or in part without prior written consent of the laboratory.
- The samples received shall be destroyed after two weeks from the date of issue of the Test Report unless specified otherwise.
- This Test Report shall not be used in any advertising media or as evidence in the court of Law without prior written consent of the laboratory.





CENTRE FOR ENVOTECH AND MANAGEMENT CONSULTANCY PVT. LTD. (LAB DIVISION)

An ISO 9001:2015, ISO 45001:2018 & ISO 14001:2015 Certified Company,

Plot No. 800/1274, Johal, Pahal, Bhubaneswar-752101, E-mail: cemclab@yahoo.in. Mobile: 9439050689

Report No. - CEMC/RM/300525/N

Issued Date-30.05.2025

NOISE LEVEL MONITORING REPORT

Issued to	M/s Kalyani Ispat Ltd., Kh No.- 585/1, Kopedeeh, Rajnandgaon, Chhatisgarh
Sample Description	Noise Level
Sample Drawn by	Mr. Bhakta Hari Das
Weather Condition	Clear
Monitoring Period	21.05.2025 to 22.05.2025
Reference No.	CEMC-300525N
Instrument Used	Noise Meter

SL No.	Location	NL Day Time dB (A)	NL Night Time dB (A)
1.	Pellet Plant	72.5	62.2
2.	Pellet Hurtment	70.4	58.3
3.	WHRB	70.2	60.1
4.	DRI	71.1	63.0

NATIONAL STANDARD OF NOISE LEVEL


Area Code	Category of Area/Zone	Permissible Limit in dB (A)	
		Day Time	Night Time
A	Industrial Area	75	70
B	Commercial Area	65	55
C	Residential Area	55	45
D	Silence Zone	50	40

BPDAS

Authorized Signatory

Notes:

- The result given above related to the tested sample, as received. The customer asked for the above test only.
- This Test Report shall not be reproduced wholly or in part without prior written consent of the laboratory.
- The samples received shall be destroyed after two weeks from the date of issue of the Test Report unless specified otherwise.
- This Test Report shall not be used in any advertising media or as evidence in the court of Law without prior written consent of the laboratory.



CEMC PVT. LTD., NABET(QCI) Accredited Category 'A' Consultant Organization.

Regd. Office: Plot No. 522/3458, Pahal, Bhubaneswar-752101, Odisha, India, Mobile: 9861032826

E-mail- cemc_consultancy@yahoo.co.in, cemc122@gmail.com, website: www.cemcpl.com

Deals with Environmental Studies (EIA & EMP), Monitoring, Forest Diversion Planning, DPR, Wildlife Management Plan, Hazardous & Safety Studies, RS & GIS, Hydrological Studies, Socio-economic Studies, DGPS & ETS Survey.

KALYANI ISPAT LIMITED

Registered Office : House No.- 117, Building No – N-18, First Floor, Sector-2, Near SBI ATM, Avanti Vihar, Raipur, Chhattisgarh, India- 492001 Phone: (06582) 256661, Fax : 91-6582-256442,
Email : rproffice@kalyaniispat.com
CIN: U27100CT2021PLC012353

Dated : 12.11.2024

ENVIRONMENTAL POLICY OF KALYANI ISPAT LIMITED

Kalyani Ispat Limited located at village – Kopedih & Anjora, P.O. – Kopedih in the Rajnandgaon district of Chhattisgarh aspires to become a globally admired organization that enhances the quality of life through sustainable development with great care for the environment and needs of the society. It is also committed to protect and improve the environment and abide by the laws & regulations concerning the environment.


The Company has laid down Environmental Policy duly approved by the Board of Directors in their meeting held on 24.08.2024. The Environmental Policy of the Company prescribes for standard operating procedures to have proper checks and balances and to bring into focus any infringement/ deviation/ violation of the environmental/ forest/ wildlife norms or conditions or of stakeholders. The copy of the board resolution along with Half Yearly Report in this regard shall be submitted to the MoEF & CC.

Our Plant is committed:

- To work towards Environment Protection, Prevention of environmental pollution, and improvement of Environment around the units.
- To adopt sound Environmental Management practices to achieve sustainable growth.
- To comply with all applicable statutory and other norms/ requirements which shall include prevention of pollution of surrounding habitation by continuous monitoring and adopting suitable measures for environmental protection.
- To implement systems to deal with environmental issues, ensuring compliance and reporting.
- To evaluate effectiveness of system through management reviews.
- To create environmental awareness among the employees and the local communities through pro-active training and communication.

For Kalyani Ispat Limited

Place: Rajnandgaon


(PRANAYA KUMAR DEO)
Director
DIN - 01566705



राजघ

अमृत संदेश

2

रायपुर, शुक्रवार 10 मई 2024

मकान नं. 79, गुलमाहर पार्क,
राम नगर, रायपुर (छ.ग.)
492001

आपका सामान तब तक इस जगह पर
जाएगा जिससे इसका लाभ
अधिक लोगों को मिल सके।

PUBLIC NOTICE REGARDING GRANT OF ENVIRONMENT CLEARANCE

The Ministry of Environment, Forest and Climate Change, Government of India, has granted Environment Clearance vide its EC Identification No. EC23A1001CG5286032N Dated 08.05.2024 for our proposed plant located at Village- Kopedih, Tehsil & District-Rajnandgaon (C.G.) for implementation of Greenfield project of Sponge Iron 660000 TPA; MS Billets 465696 TPA; Rolled Steel Products through Hot Charging & Reheating Furnace 478500 TPA; Iron Ore Pellets 1.2 MTPA; SAF to produce SiMn 36000 TPA and/or FeMn 46000 TPA; and/or FeSi 22,500 TPA and/or Pig iron 63000 TPA; Captive Power of 75MW (50MW thru WHRB & 25MW thru CFBC); Pipe Mill 155100 TPA; Galvanized Mill 155100 TPA; and Fly Ash Bricks 41500 TPA; . The copy of the same is available at Ministries website (www.parivesh.nic.in) as well as RO (Durg) and HO (Nava Raipur) of Chhattisgarh Environment Conservation Board.
Place: Rajnandgaon (C.G.)
Date: 09.05.2024

M/s. Kalyani Ispat Limited
Village-Kopedih, Tehsil & District-Rajnandgaon (C.G.)

NOTICE

U/s 72 OF THE INDIAN PARTNERSHIP ACT, 1932

Notice is hereby given that the following changes have occurred in M/s GUJRAT MILL STORES, M.G. ROAD RAIPUR (C.G.), Shri Asgar Ali retired from the partnership w.e.f. 31.03.1994.

सो-11
गायत्री
(नं. -04,
बसना
(छ.ग.)
सर्वस
जाता है

(HUSSAIN) आरंग,
निवासी (छ.ग.)
आबिद मे
के सामने क्रमांक./ब 121
पो.आ. रा ग्राम - कोरासी
(छ.ग.) सर्वसाधारण को
करता हूँ कि आवेदक
नाम समूह ग्राम
हुसैन अली द्वारा आवेदन
समीना अली का
हुसैन अली
आज से 2017 है, का
शासकीय जन्म मृत्यु को
दस्तावेजों द्वारा प्रमाणित किया है, ताकि
समीना अली आवेदक को प्राप्त
हुसैन अली
जावे।

है व्यक्ति को
न्यायालय में
समर्पित प्रस्तुत
पिता के बाद प्राप्त
मकान नं. 30
नहीं किया

योगासन स्वस्थ और अनुशासित बनाता है: साहू

गुडवारा स्थित कार्यालय में दस्तावेज
सहित स्वयं अथवा अपने वैध अभिभावक
के माध्यम से उपस्थित होकर प्रस्तुत कर
सकते हैं। बाद के किसी दावा या आपत्ति
पर विचार किया जाना संभव नहीं होगा।
अतः सूचना जानें।

राजस्व निरीक्षक
रायपुर 04

पहचाना जावे।

बाबू भाई पटेल

86 जीएच आर के पटेल एंड

कम्पनी सरदार टिम्बर मार्केट

भनपुरी रायपुर (छ.ग.) 49200

न्यायालय तहसीलदार आरंग,
जिला रायपुर (छ.ग.)
ईशतहार

राजस्व प्रकरण क्रमांक./ब 121
ग्राम - भैंसा

एतद् द्वारा सर्वसाधारण को

सूचित किया जाता है कि आवेदक गायत्री
साहू पिता श्री पुनितराम साहू ग्राम भैंसा
तहसील आरंग, द्वारा आवेदन प्रस्तुत कर
अपने पुत्री स्मिता साहू के जन्म/मृत्यु
दिनांक 05.11.1992 है, का पंजीयन
कराने हेतु पंजीयक जन्म मृत्यु को आदेश
जारी करने की मांग किया है, ताकि
जन्म/मृत्यु का प्रमाण पत्र आवेदक को प्राप्त
हो सके।

उपरोक्त संबंध में जिस किसी व्यक्ति को
दावा/ आपत्ति हो तो वे इस न्यायालय में
दिनांक 20.05.2024 तक आपत्ति प्रस्तुत
कर सकते हैं। नियत तिथि के बाद प्राप्त
आपत्ति पर कोई विचार नहीं किया

न्यायालय तहसीलदार आरंग,
जिला रायपुर (छ.ग.)
ईशतहार


राजस्व प्रकरण क्रमांक./ब 1
ग्राम - केश

एतद् द्वारा सर्वसाधारण को

सूचित किया जाता है कि आवेदक
लिलाधर पिता नंदू ग्राम केशला तहसील
आरंग, द्वारा आवेदन प्रस्तुत कर अप
पुत्री कुमकुम के जन्म दिनांक
16.05.2013 है, का पंजीयन कराने हे
पंजीयक जन्म को आदेश जारी करने व
मांग किया है, ताकि मृत्यु का प्रमाण प
आवेदक को प्राप्त हो सके।

उपरोक्त संबंध में जिस किसी व्यक्ति क
दावा/ आपत्ति हो तो वे इस न्यायालय में
दिनांक 20.05.2024 तक आपत्ति प्रस्तुत
कर सकते हैं। नियत तिथि के बाद प्राप्त
आपत्ति पर कोई विचार नहीं किया

साथ 5 छात्राओं ने बनाया टॉप टेन में स्थान



हायर सेकण्डरी परीक्षा में कुल 12734
पंजीकृत हुये। इनमें से 5343 बालक,
7278 बालिकायें कुल 12621 परीक्षार्थी

ई भगवान
समें तिल्या
य नागरिक
ग्रसाइकिल
० नगर के
भवन में
चौक स्थित
न्यापण कर
काफ़े संख्या

यथावत कोरिया वेंसरकोरी अस्पताल में डॉक्टर के पर्दे पर जाकर वह बुधवार को वह परिवार के साथ कार क्रमांक सीजी 10 बीक्यू 1042 से कोरिया से बिलासपुर जा रही थी। शाम लगभग साढ़े पांच बजे गुरसियाँ के पास स्वराज माजड़ा क्रमांक सीजी 12 बीबी 7393 के चालक ने उसकी कार को टोकर मार दी। हादसे में श्रुति की कार अनियंत्रित हो गई और सड़क किनारे रेलिंग से जा टकराई। घटना में कार में सवार सभी बाल-बाल बच गए। बताया जा रहा है कि एक बच्चे को मामूली चोट आई है। स्थानीय लोगों ने पिकअप को रोकवाया और चालक को पकड़ा। पूछताछ में उसने अपना नाम सतीश यादव निवासी गनियारी चौरभट्टी बताया, जबकि वाहन स्वामी का नाम धर्मेद कुमार बताया जा रहा है।

जेल बलीदाबाजार में परिरूढ़ 65 बंदियों का आयुर्वेद पद्धति से इलाज किया गया। बंदियों एवं जेल स्टॉफपुराना सर्दी खांसी, चर्मरोग, उदररोग, ब्लड प्रेसर, शुगर रोग का आयुर्वेद पद्धति से रहन-सहन, खान-पान पथ्य-अपथ्य की जानकारी एवं दवाई दी गई। जिला आयुर्वेद अधिकारी डॉ. गोदावरी पैकर ने बताया कि संचालनालय आयुष के निर्देशानुसार प्रदेश के समस्त जेलों में स्वास्थ्य शिविरों का आयोजन परिरूढ़ बंदियों के समुचित उपचार व्यवस्था हेतु निर्देशित किया गया है। इस अवसर पर शिविर में वरिष्ठ चिकित्सक डॉ. एल. एस. ध्रुव, फर्मासिस्ट विनोद कुरें, औषधालय सेवक योगेंद्र गेंड्रे उपस्थित रहे।

लिए दिया धन्यवाद

ताओं के प्रति जताया आभार

के साथ कंधे से कंधा मिलाकर मतदान की इस प्रक्रिया को निष्पक्ष-शांतिपूर्ण ढंग से संपन्न कराने में अपनी महत्वपूर्ण भूमिका निभाई है। उन्होंने सभी अधिकारी-कर्मचारियों को इसके लिए अपनी बधाई और शुभकामनाएं दी।

उन्होंने चुनाव जैसे राष्ट्रीय महत्व के कार्य में सहयोग करने वाले शासकीय अधिकारियों, कर्मचारियों, सुरक्षा बलों, होमगार्ड सहित अन्य सभी व्यक्तियों जिन्होंने सम्प्रतापूर्वक और निष्पक्ष स्वतंत्र तथा शांतिपूर्ण चुनाव में अपना अमूल्य सहयोग दिया है। कलेक्टर चौहान ने सभी के प्रति धन्यवाद ज्ञापित करते हुए उनका


आभार जताया है। जिला निर्वाचन अधिकारी के एल चौहान ने इलेक्ट्रॉनिक और प्रिंट, सोशल मीडिया के प्रतिनिधियों के द्वारा चुनाव कार्य से संबंधित महत्वपूर्ण सूचनाओं को अभ्यर्थियों, आम जनता तक पहुंचाने तथा चुनाव कार्य में सहयोग के लिए उनके प्रति अपना आभार जताया है। उन्होंने कहा कि निर्वाचन संबंधी प्रक्रणा की जानकारी लोगों तक पहुंचाने के साथ-साथ बलौदाबाजगर भाटापुरा जिले में चुनाव के दौरान कोई भ्रामक खबर या अपवाद को फैलने से रोकने में जिला प्रशासन को मीडिया का बेहतर सहयोग मिला।

पर्यावरण स्वीकृति बाबत आम सूचना

एतद् द्वाय सर्व संरक्षण को सुस्थित किया जाता है कि भारत सरकार पार्षवार्ण, वन एवं जलवायु परिवर्तन मंत्रालय में ई.आर.ए. अधिसूचना 2006 के अंतर्गत अपने ईसी पक्षीजन नंबर EC23A1001CG5E286032N Dated 08.05.2006 के द्वाय हमारे ग्राम-कोषीयों, लहरीसी एवं जिला-राजधानीयों (छ.ग.) में परस्ताति प्रोफेक्टिव परियोजना के तहत समय आगमन श्रमता 6,60,000 टन/वर्ष, पार.एस. फिल्टरद श्रमता 4,65,696 टन/वर्ष, रिहाइल स्टील प्रोडक्ट्स यू.होट चार्जिंग एवं इलिटिंग श्रमता 3,78,500 टन/वर्ष, आगमन ओर पेलेट्स श्रमता 12 मिथियन टन/वर्ष, पार.एफएस से प्रोड्यूस सिलिको मैगनीजुम श्रमता 36,000 टन/वर्ष और/या फेरो सिलिको श्रमता 22,500 टन/वर्ष और/या पिता आगमन श्रमता 63,000 टन/वर्ष, कैस्टल पिलर 75 मेगावट (50 मेगावट यू ज्यूम्पुलरआओ एवं 25 मेगावट यू रोपफनीबीसी), थार्पि पिलर श्रमता 1,55,100 टन/वर्ष, मैल्नोब्राइड मिल श्रमता 1,55,100 टन/वर्ष एवं फाईर एंड ब्रिक्स श्रमता 41,500 टन/वर्ष को परीयोजना हेतु पार्षवार्ण स्वीकृति प्रदाय किया है। जिसको प्रति पार्षवार्ण, वन एवं जलवायु परिवर्तन मंत्रालय को वेबसाइट (www.parivesh.nic.in) तथा प्रतिस्तिपि छत्तीसगढ़ पार्षवार्ण संरक्षण मंडल, क्षेत्रीय कार्यालय दुर्ग तथा मुख्यालय अटल नगर, नवा राणपुर में भी अवलोकने हेतु उपलब्ध है।

स्थान:- राजनांदगांव (छ.ग.)
दिनांक:- 09.05.2024

मेसर्स कल्याणी इस्पात लिमिटेड
ग्राम-कोपेडोह, तहसील एवं जिला-राजनांदगांव
(छ.ग.)

[illegible]

ਸ਼ਿਲਪ ਸ਼ਿਲਪੀ ਤੇ ਪੁਰ, ਸ਼ਿਲਪੀ ਤੇ ਪੁਰ

[illegible]

क्रमांक : कल्याणी इस्पात / ईसी / 2024

दिनांक : 09 मई, 2024

प्रति

 श्रीमान कलेक्टर महोदय
 जिला राजनांदगांव (छ.ग.)

विषय : परियोजना में पर्यावरण स्वीकृति की सूचना बाबत।

माननीय महोदय,

इस पत्र के माध्यम से आपको सविनय सूचित करते हैं कि भारत सरकार पर्यावरण, वन एवं जलवायु परिवर्तन मंत्रालय ने ई.आई.ए. अधिसूचना 2006 के अंतर्गत मेसर्स कल्याणी इस्पात लिमिटेड, ग्राम-कोपेडीह, तहसील एवं जिला-राजनांदगांव (छ.ग.) में प्रस्तावित ग्रीनफील्ड परियोजना हेतु अपने ईसी पहचान नंबर- **EC23A1001CG5286032N Dated 08.05.2024** द्वारा पर्यावरण स्वीकृति जारी की है। जिसकी प्रति संलग्न है।

उपरोक्त पर्यावरण स्वीकृति में उल्लेखित (B) जनरल कंडिशन के बिन्दु क्रमांक (X) मिसलेनियस के शर्त क्रमांक (ii) के अनुपालन के स्वरूप में आपके कार्यालय को इस पर्यावरण स्वीकृति की सूचना प्रदान की जा रही है।

साथ ही पर्यावरण स्वीकृति की शर्तों के अपेक्षानुसार आपसे निवेदन है इसकी सूचना आपके कार्यालय के नोटिश बोर्ड में 30 दिनों के लिए प्रदर्शित करने की कृपा करें।

आशा है आपके अपेक्षित सहयोग प्राप्त होगा।

सधन्यवाद एवं सादर

भवदीय

मेसर्स कल्याणी इस्पात लिमिटेड


 (संचालक)

संलग्न : पर्यावरण स्वीकृति की छायाप्रति।

प्रतिलिपि:

1. श्रीमान सदस्य सचिव, छ.ग. पर्यावरण संरक्षण मंडल पर्यावास भवन, अटल नगर, नवा रायपुर (छ.ग.)।
2. श्रीमान क्षेत्रीय अधिकारी, क्षेत्रीय कार्यालय, छ.ग.प.सं.मं., भिलाई, दुर्ग (छ.ग.)।
3. श्रीमान सरपंच महोदय, ग्राम पंचायत, कोपेडीह।

